

SITE DEVELOPMENT PLANS FOR OVER 55 RESIDENTIAL DEVELOPMENT 470 BOSTON STREET TOPSFIELD, MA

OWNER\APPLICANT:
SARKIS DEVELOPMENT COMPANY
2 ELM SQUARE
ANDOVER, MA 01810
978.475.4055

(NOT TO SCALE)

ARCHITECT:
THE MZO GROUP
335 MAIN STREET, SUITE 201
STONEHAM, MA 02180
781.279.4446

LAND SURVEYOR & CIVIL ENGINEER
ALLEN & MAJOR ASSOCIATES, INC.
100 COMMERCE WAY
WOBURN, MA 01888-0118
781.935.6889


SANITARY SEWER ENGINEER: EAGLEBROOK ENGINEERING AND SURVEY, LCC 491 MAPLE STREET, SUITE 304 DANVERS, MA 01923 978.777.0494

LANDSCAPE ARCHITECT:
BROWN SARDINA
24 ROLAND STREET
BOSTON, MA 02129
617.482.4703

TRAFFIC ENGINEER:
VANASSE & ASSOCIATES, INC.
35 NEW ENGLAND BUSINESS CENTER DRIVE
SUITE 140
978.688.6508

WETLAND SCIENTIST:
SEEKAMP ENVIRONMENTAL CONSULTANTS
129 ROUTE 125
KINGSTON, NH 03848
603.642.8300







TEL: (781) 935-6889 FAX: (781) 935-2896

WOBURN, MA . LAKEVILLE, MA . MANCHESTER, NH




CIVIL LIST O	F DRAWIN	IGS	
DRAWING TITLE	SHEET NO.	ISSUED	LAST REVISED
EXISTING CONDITIONS PLAN	- 1	10-13-2016	
ABBREVIATIONS & NOTES	ABB-I - ABB-3	10-13-2016	
DEMOLITION & EROSION CONTROL PLAN	C-I	10-13-2016	
LAYOUT & MATERIALS PLAN	C-2	10-13-2016	
GRADING & SPOT GRADES PLAN	C-3A - C3B	10-13-2016	
DRAINAGE PLAN	C-4A - C4-B	10-13-2016	
DRAINAGE PROFILES	C-4C - C-4D	10-13-2016	
WATER & GAS UTILITIES PLAN	C-5A	10-13-2016	
SITE ELECTRIC PLAN	C-5B	10-13-2016	
FIRE TRUCK TURNING PLAN	C-6	10-13-2016	
SNOW STORAGE PLAN	C-7	10-13-2016	
TEST PITS PLAN	TPP-I	10-13-2016	
DETAILS	D-I - D-9	10-13-2016	

LANDSCAPE ARCHIT	ECTS LIST (OF DRAW	/INGS
DRAWING TITLE	SHEET NO.	ISSUED	LAST REVISED
PLANTING AND LIGHTING PLAN	L-I	10-13-2016	
PLANT LIST AND SEEDING PLAN	L-2	10-13-2016	

SANITARY S	EWER LIST OF D	RAWING	S
DRAWING TITLE	SHEET NO.	ISSUED	LAST REVISED
SDS PLAN	SDS-I	10-13-2016	
SDS PLAN	SDS-1.1	10-13-2016	
SDS PLAN	SDS-2.1	10-13-2016	V 12
SDS PLAN	SDS-3.1	10-13-2016	
SDS PLAN	SDS-4	10-13-2016	
SDS PLAN	SDS-5	10-13-2016	

LIST OF D	RAWING	S
SHEET NO.	ISSUED	LAST REVISED
COVER	10-05-16	
A-I	10-05-16	
A-2	10-05-16	
A-3	10-05-16	
A-4	10-05-16	
A-5	10-05-16	
A-6	10-05-16	
A-7	10-05-16	400 000 UA 400 000 US 400 US 400 US
A-8	10-05-16	
A-9	10-05-16	
A-10	10-05-16	
A-II	10-05-16	
A-12	10-05-16	
	SHEET NO. COVER A-I A-2 A-3 A-4 A-5 A-6 A-7 A-8 A-9 A-10 A-11	COVER 10-05-16 A-1 10-05-16 A-2 10-05-16 A-3 10-05-16 A-4 10-05-16 A-5 10-05-16 A-6 10-05-16 A-7 10-05-16 A-8 10-05-16 A-9 10-05-16 A-10 10-05-16 A-11 10-05-16

ISSUED FOR SPECIAL PERMIT,
SITE PLAN REVIEW & NOTICE OF INTENT:
OCTOBER 13, 2016




WE HEREBY CERTIFY THAT:

THIS PLAN IS THE RESULT OF AN ACTUAL ON THE GROUND SURVEY PERFORMED ON OR BETWEEN JUNE 30, 2016 AND JULY 12, 2016 THIS PLAN WAS PREPARED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE REGISTERS OF DEEDS DATED JANUARY 1, 1976 AND REVISED JANUARY 12, 1988. ACCORDING TO DEEDS AND PLANS OF RECORD, THE PROPERTY LINES SHOWN ON THIS PLAN ARE THE LINES DIVIDING EXISTING OWNERSHIP, AND THE LINES OF THE STREETS OR WAYS SHOWN ARE THOSE OF PUBLIC OR PRIVATE STREETS AND WAYS ALREADY ESTABLISHED, AND THAT NO NEW LINES FOR THE DIVISION OF EXISTING OWNERSHIP OR FOR

NEW WAYS ARE SHOWN. THE ABOVE CERTIFICATION IS INTENDED TO MEET REGISTRY OF DEEDS REQUIREMENTS FOR THE RECORDING OF PLANS AND IS NOT A CERTIFICATION TO THE TITLE OR OWNERSHIP OF THE PROPERTY SHOWN. OWNERS OF ADJOINING PROPERTIES ARE SHOWN ACCORDING TO CURRENT TOWN OF TOPSFIELD AND TOWN OF IPSWICH ASSESSORS'

INFORMATION. THE ABOVE IS CERTIFIED TO THE BEST OF MY PROFESSIONAL KNOWLEDGE, INFORMATION AND BELIEF.

ALLEN & MAJOR ASSOCIATES, INC.



1.	10/13/16	FLOOD ZONE LINE ADDED
REV	DATE	DESCRIPTION
	NITA ONA/AIED.	

APPLICANT\OWNER:

SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE ANDOVER, MA 01810

PROJECT:

470 BOSTON STREET (ROUTE 1) TOPSFIELD, MA

PROJECT NO. 2165-01A DATE: 08/02/16 1" = 60' DWG. NAME: S-2165-01A-EC

COB\MSM | CHECKED BY: DRAFTED BY:



ASSOCIATES, INC.

civil & structural engineering + land surveying environmental consulting + landscape architectur www.allenmajor.com 100 COMMERCE WAY P.O. BOX 2118

WOBURN MA 01888-0118 TEL: (781) 935-6889 FAX: (781) 935-2896 WOBURN, MA . LAKEVILLE, MA . MANCHESTER, NH

THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT. CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETI MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT, DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD COPIES OF

DRAWING TITLE:

SHEET No.

Copyright@2016 Allen & Major Associates, Inc.

EXISTING CONDITIONS

GENERAL NOTES:

- FOR EXISTING CONDITIONS SURVEY, SEE PLAN ENTITLED "EXISTING CONDITIONS", AS PREPARED BY ALLEN & MAJOR ASSOCIATES, INC. THE ON THE GROUND SURVEY WAS PERFORMED ON OR BETWEEN JUNE 30, 2016 & JULY 12, 2016.
- 2. ZONING DISTRICT IS BUSINESS PARK DISTRICT (BP), AS WELL AS AN ELDERLY HOUSING DISTRICT (EHD) OVERLAY, TOPSFIELD, AND INDUSTRIAL (I) IN IPSWICH.
- 3. PER THE TOWN OF TOPSFIELD ENGINEERING DEPARTMENT, IT IS THE CONTRACTOR'S RESPONSIBILITY TO:
 - SCHEDULE A PRECONSTRUCTION MEETING WITH THE TOPSFIELD ENGINEERING DEPARTMENT TO REVIEW THE CONSTRUCTION SCHEDULE, PERMITTED DRAWINGS AND PERMIT CONDITIONS AT LEAST ONE (1) WEEK PRIOR TO THE COMMENCEMENT OF EARTH DISTURBING ACTIVITIES AT NO ADDITIONAL COST TO OWNER.
 - GIVE REASONABLE NOTICE TO THE TOPSFIELD ENGINEERING DEPARTMENT FOR INSPECTION PRIOR TO INSTALLING ANY PROPOSED STORMWATER MANAGEMENT SYSTEMS OR INSTALLATION OF ANY OTHER CRITICAL DESIGN COMPONENTS IDENTIFIED DURING THE ABOVE MENTIONED PRECONSTRUCTION MEETING.
 - PROVIDE AS—BUILT PLANS IN ACCORDANCE WITH THE TOWN OF TOPSFIELD STORMWATER MANAGEMENT REGULATIONS.
- 4. OVERALL LOT SIZE: 16.32± ACRES. TOWN OF TOPSFIELD ASSESSORS MAP #7 PARCEL #3. TOWN OF IPSWICH ASSESSORS MAP # 49 PARCELS # 1 & #2.
- 5. DURING CONSTRUCTION, ALL VEHICLES MUST BE PARKED ON SITE.
- 6. DURING CONSTRUCTION, ALL STAGING AND DELIVERIES WILL OCCUR ON SITE.
- 7. EXTERIOR CONSTRUCTION ACTIVITIES ON THE SITE SHALL FOLLOW ALL APPLICABLE REGULATIONS PER THE TOWN OF TOPSFIELD, AS IT RELATES TO CONSTRUCTION HOURS, NOISE AND CONSTRUCTION SCREENING AND FENCING.
- 8. THIS PROJECT WILL BE SERVED BY PUBLIC WATER, NATURAL GAS, TELEPHONE, CABLE AND ELECTRIC. ALL UTILITY LINES WILL BE INSTALLED UNDERGROUND UNLESS OTHERWISE NOTED.
- 9. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AND STRUCTURES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF VARIOUS UTILITY COMPANIES AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE LOCATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR MUST CONTACT THE APPROPRIATE UTILITY COMPANY, ANY GOVERNING PERMITTING AUTHORITY, AND "DIGSAFE" AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION WORK TO REQUEST EXACT FIELD LOCATION OF UTILITIES AND THE ENGINEER SHALL BE NOTIFIED IN WRITING OF ANY UTILITIES INTERFERING WITH THE PROPOSED CONSTRUCTION AND APPROPRIATE REMEDIAL ACTION TAKEN BEFORE PROCEEDING WITH THE WORK. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS AT NO ADDITIONAL COST.
- 10. ALL MAIN BUILDING ENTRANCES AND WALKS SHALL BE HANDICAP ACCESSIBLE PER FEDERAL ADA & MA AAB REGULATIONS AT NO ADDITIONAL COST TO THE OWNER.
- 11. ALL SITE WORK DONE FOR THIS PROJECT SHALL BE IN STRICT ACCORDANCE WITH THE SITE PLANS AND SITE WORK SPECIFICATIONS FOR CONSTRUCTION.
- 12. ANY DAMAGE TO PRIVATE OR PUBLIC PROPERTIES DUE TO THE CONTRACTOR'S ACTIVITIES SHALL BE REPAIRED AND RESTORED BY THE CONTRACTOR AT THEIR OWN EXPENSE.
- 13. ALL PROPERTY MARKERS AND STREET LINE MONUMENTS SHALL BE PROPERLY PROTECTED DURING CONSTRUCTION. ANY DAMAGE TO THESE ITEMS SHALL BE REPAIRED AND RESTORED BY A SURVEYOR REGISTERED IN THE STATE OF MASSACHUSETTS AT THE CONTRACTOR'S EXPENSE.
- 14. ALL APPLICABLE PERMITS AND AN APPROVED SET OF PLANS SHALL BE AVAILABLE AT THE CONSTRUCTION SITE.
- 15. THE CONTRACTOR IS RESPONSIBLE FOR SCHEDULING A PRECONSTRUCTION MEETING THE WITH THE APPROPRIATE TOWN DEPARTMENTS, THE APPROPRIATE UTILITY COMPANIES, THE OWNER AND OWNER'S REPRESENTATIVE. THE MEETING SHALL TAKE PLACE PRIOR TO THE START OF CONSTRUCTION AND THE CONTRACTOR MUST PROVIDE 48 HOURS NOTICE TO ALL ATTENDEES PRIOR TO THE START OF THE MEETING.
- 16. APPROPRIATE WARNING SIGNS, MARKERS, BARRICADES AND/OR FLAG MEN SHALL BE PROVIDED TO REGULATE TRAFFIC. CONSTRUCTION TRAFFIC CONTROLS SHALL BE IMPLEMENTED AND OPERATED ACCORDING TO THE MASS DEPARTMENT OF TRANSPORTATION, THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) AND THE LOCAL AUTHORITY.
- 17. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ADDITIONAL BENCHMARK INFORMATION IF REQUIRED. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING AND PROTECTING ALL EXISTING BENCHMARKS. IF IT IS NECESSARY TO RELOCATE A BENCHMARK, IT SHALL BE RELOCATED BY A MASSACHUSETTS PROFESSIONAL LAND SURVEYOR AND DONE SO AT THE CONTRACTOR'S EXPENSE.
- 18. ALL BUILDING DIMENSIONS ARE MEASURED TO THE OUTSIDE FACE OF THE BUILDING.
- 19. ALL RADII ARE 3 FEET UNLESS OTHERWISE NOTED.
- 20. ALL PARKING LOT AND AISLE DIMENSIONS ARE TAKEN FROM THE FACE OF CURB AND INDICATE EDGE OF PAVEMENT.
- 21. CONSTRUCTION DURING WET WEATHER OR WINTER CONDITIONS IS TO BE ANTICIPATED AND PROVISIONS TO ADEQUATELY ADDRESS THESE CONDITIONS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AT NO ADDITIONAL COST.
- 22. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND PAYING FOR ANY PERMITS AND/OR CONNECTION FEES REQUIRED TO CARRY OUT THE WORK INCLUDING BUT NOT LIMITED TO DEMOLITION.
- 23. DISPOSAL OF ALL DEMOLISHED MATERIALS INCLUDING EXISTING MISC. CONSTRUCTION DEBRIS FILL IS THE RESPONSIBILITY OF THE CONTRACTOR AND MUST BE DISPOSED OF OFF—SITE IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL MUNICIPAL REQUIREMENTS AT NO ADDITIONAL COST.
- 24. ALL DISTURBED AREAS NOT NOTED TO RECEIVE OTHER TREATMENT ARE TO RECEIVE SIX INCHES (6") MINIMUM OF TOPSOIL & SEED, AND BE MAINTAINED UNTIL ESTABLISHED & ACCEPTED.
- 25. EXISTING STRUCTURES WITHIN CONSTRUCTION LIMITS ARE TO BE ABANDONED, REMOVED OR RELOCATED AS NECESSARY.
- 26. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL RELOCATIONS, INCLUDING BUT NOT LIMITED TO, ALL UTILITIES, STORM DRAINAGE, SIGNS, TRAFFIC SIGNALS & POLES, ETC. AS REQUIRED. ALL WORK SHALL BE IN ACCORDANCE WITH THE TOWN OF TOPSFIELD'S GOVERNING AUTHORITY'S SPECIFICATIONS AND SHALL BE APPROVED BY SUCH.
- 27. THE CONTRACTOR SHALL COORDINATE WITH ALL UTILITY COMPANIES TO DETERMINE EXACT POINT OF SERVICE CONNECTION AND DISCONNECTION AT EXISTING UTILITY.
- 28. ALL ELEVATIONS SHOWN ARE IN REFERENCE TO THE BENCHMARK AND MUST BE VERIFIED BY THE GENERAL CONTRACTOR AT GROUNDBREAKING.
- 29. EXISTING AND PROPOSED GAS SERVICE LOCATIONS ARE APPROXIMATE ONLY. THE CONTRACTOR SHALL CONFIRM WITH THE GAS COMPANY THAT THE GAS LINE INSTALLATION & DISCONNECTION SHALL BE BY THE LOCAL GAS COMPANY. THE CONTRACTOR SHALL GIVE THE GAS COMPANY ADVANCE NOTICE OF WHEN THE GAS LINE CAN BE INSTALLED.

GENERAL NOTES (CONTINUED):

- 30. EXISTING & PROPOSED ELECTRIC AND COMMUNICATIONS (TELEPHONE AND CABLE) SYSTEMS LOCATIONS ARE APPROXIMATE ONLY AND SHALL BE COORDINATED AND SCHEDULED WITH THE APPROPRIATE UTILITY COMPANY SERVICING THE PROJECT SITE.
- 31. CONTRACTOR IS RESPONSIBLE FOR DIGGING TEST HOLES AND VERIFYING ANY EXISTING UTILITY OR STRUCTURE PRIOR TO CONSTRUCTION. CONTRACTOR SHALL VERIFY THAT BASED ON EXACT LOCATION OF EXISTING UTILITIES, THERE ARE NO CONFLICTS BETWEEN THEM AND THE PROPOSED UTILITIES.
- 32. THE CONTRACTOR SHALL ADHERE TO ALL PERMIT CONDITIONS PROVIDED BY ALL GOVERNING AGENCIES AT NO ADDITIONAL COSTS. THIS INCLUDES BUT IS NOT LIMITED TO BUILDING PERMITS, DEMOLITION PERMITS, PLUMBING, GAS, AND ELECTRICAL PERMITS.
- 33. THE CONTRACTOR SHALL BE FAMILIAR WITH AND ADHERE TO THE TOPSFIELD CONSERVATION COMMISSION'S ORDER OF CONDITIONS (OOC), TOPSFIELD PLANNING BOARD DECISION, AND TOPSFIELD ZONING BOARD OF APPEALS DECISION, CONDITIONS, AND REQUIREMENTS AT NO ADDITIONAL COST TO OWNER.
- 34. IT IS THE CONTRACTORS RESPONSIBILITY TO PROPERLY DISPOSE OF AND ABATE ALL BUILDING MATERIALS OR ANY HAZARDOUS MATERIALS ONSITE IN ACCORDANCE WITH ALL STATE, FEDERAL, AND LOCAL LAWS AND REGULATIONS AT NO ADDITIONAL COST TO THE OWNER.
- 35. DURING EXCAVATION, ANY EXISTING LOAM WHICH DOES NOT MEET THE STANDARD LOAM DETAIL SHALL BE REMOVED OFFSITE BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE

GRADING & DRAINAGE NOTES:

- 1. EXISTING PAVEMENT SHALL BE SAW-CUT AND PAVEMENT JOINT SHALL BE INSTALLED WHERE NECESSARY TO ENSURE A SMOOTH CONTINUOUS GRADE.
- 2. THE ARCHITECTURAL PLANS SHALL BE REFERRED TO IN ORDER TO DETERMINE THE EXACT LOCATIONS OF VESTIBULE, SLOPED PAVING, EXIT PORCHES, HANDICAPPED RAMPS, TRUCK DOCKS. COMPACTOR PAD, ROOF DRAIN LATERALS AND PRECISE BUILDING DIMENSIONS.
- ALL GRADING OPERATIONS SHALL BE COORDINATED WITH THE APPROPRIATE UTILITY COMPANIES.
- 4. IN LANDSCAPED AREAS THE TOP ELEVATION OF MANHOLES SHALL MATCH THE FINISH GRADE OF THE TOPSOIL. IN PAVED AREAS THE TOP ELEVATIONS OF MANHOLES SHALL MATCH FINISH GRADE.
- 5. ALL AREAS DISTURBED DURING CONSTRUCTION SHALL BE STABILIZED AS SOON AS POSSIBLE UPON COMPLETION OF CONSTRUCTION WORK IN THE AREA.
- 5. TEMPORARY STRAW BALE PROTECTION AND/OR SILT SACK SHALL BE INSTALLED AND MAINTAINED AT EXISTING DRAINAGE STRUCTURES DURING CONSTRUCTION, TO PREVENT SEDIMENT LADEN RUNOFF FROM ENTERING THE DRAINAGE SYSTEM. SILT SACKS ARE REQUIRED AT ALL EXISTING DRAINAGE STRUCTURE INLETS DURING CONSTRUCTION.
- 7. CONTRACTOR IS RESPONSIBLE FOR DEMOLITION OF EXISTING STRUCTURES INCLUDING REMOVAL OF ANY EXISTING UTILITIES SERVING THE STRUCTURE.
- 3. ALL CATCH BASINS, MANHOLES, INFILTRATION SYSTEM, AND WATER QUALITY STRUCTURES ARE TO BE CLEANED OUT PRIOR TO FINAL APPROVAL TO REMOVE ALL CONSTRUCTION SILT AND DEBRIS
- 9. IF ANY EXISTING UTILITY STRUCTURES TO REMAIN ARE DAMAGED DURING CONSTRUCTION IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR AND/OR REPLACE THE EXISTING STRUCTURE AS NECESSARY TO RETURN IT TO EXISTING CONDITIONS OR BETTER AT NO ADDITIONAL COST.
- ALL STORM PIPE ENTERING STRUCTURES SHALL BE GROUTED TO ASSURE CONNECTION AT STRUCTURE IS WATERTIGHT.
- 11. ALL STORM DRAIN MANHOLES SHALL HAVE TRAFFIC BEARING RING & COVERS & SHALL BE LABELED "DRAIN".
- 12. THE CONTRACTOR SHALL ADHERE TO ALL TERMS & CONDITIONS AS OUTLINED IN THE GENERAL N.P.D.E.S. PERMIT FOR STORM WATER DISCHARGE ASSOCIATED WITH CONSTRUCTION ACTIVITIES.
- 13. CONTRACTOR SHALL ASSURE POSITIVE DRAINAGE AWAY FROM BUILDINGS FOR ALL NATURAL AND PAVED AREAS.
- 14. ALL UNSURFACED AREAS DISTURBED BY GRADING OPERATION SHALL RECEIVE SIX INCHES (6") OF TOPSOIL. CONTRACTOR SHALL GRASS DISTURBED AREAS IN ACCORDANCE WITH LANDSCAPE & CIVIL SPECIFICATIONS & DRAWINGS UNTIL A HEALTHY STAND OF GRASS IS OBTAINED.
- 15. CONTRACTOR SHALL APPLY STABILIZATION FABRIC TO ALL SLOPES 3H:1V OR STEEPER.
- 16. ALL DRAINAGE SHALL CONFORM TO LOCAL REQUIREMENTS.

UTILITY NOTES:

- THE LATEST STANDARDS OF THE TOWN OF TOPSFIELD SHALL BE FOLLOWED WHEN INSTALLING ANY SANITARY SEWER AND STORM DRAIN WORK. BOTH SEWER AND STORM DRAIN WORK WILL BE INSPECTED BY TOWN OF TOPSFIELD PERSONNEL AND ALL COSTS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 2. THE LATEST STANDARDS OF THE TOWN OF TOPSFIELD SHALL BE FOLLOWED WHEN INSTALLING ANY WATER LINE WORK. WATER LINE WORK WILL BE INSPECTED BY TOWN OF TOPSFIELD PERSONNEL AND ALL COSTS SHALL INCLUDE PRESSURE TESTING, DISINFECTING, AND FLUSHING OF LINES. INSPECTION COSTS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSTALLATION AND REMOVAL OF ALL NECESSARY DISINFECTING AND FLUSHING TAPS AS DIRECTED BY THE TOWN.
- THE CONTRACTOR SHALL REFER TO ARCHITECTURAL & PLUMBING DRAWINGS AND SPECIFICATIONS FOR ACTUAL LOCATION OF ALL ROOF DRAIN LATERALS AND UTILITY ENTRANCES TO INCLUDE SANITARY SEWER LATERALS, DOMESTIC AND FIRE PROTECTION WATER SERVICE, ELECTRIC, TELEPHONE, AND NATURAL GAS SERVICE. THE CONTRACTOR SHALL COORDINATE INSTALLATION OF UTILITIES IN SUCH A MANNER AS TO AVOID CONFLICTS AND COORDINATE WITH THE PROPER AGENCY THE LOCATION AND SCHEDULING OF CONNECTIONS WITH THEIR FACILITIES.
- 4. WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, THE LOCATION, ELEVATION AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR, AND THE INFORMATION FURNISHED TO THE ENGINEER FOR RESOLUTION.
- 5. ABANDONED EXISTING UTILITIES AND UTILITIES TO BE ABANDONED SHALL EITHER BE ABANDONED IN PLACE AS NOTED OR SHALL BE REMOVED AND DISPOSED OF AS SPECIFIED. ANY UTILITIES 4" OR LARGER ARE TO BE REMOVED. ALL UTILITIES SCHEDULED FOR ABANDONMENT OR REMOVAL AND DISPOSAL MUST BE COORDINATED BY THE CONTRACTOR WITH THE RESPECTIVE UTILITY OWNER. WHEN ABANDONED UTILITIES ARE TO BE LEFT IN PLACE, PLUG OR CAP THE ENDS OF THE CONDUITS AND PIPES. REMOVE ABANDONED UTILITY MANHOLES, JUNCTION BOXES AND SIMILAR STRUCTURES TO A MINIMUM DEPTH OF 4 FEET BELOW FINISHED GRADE AND PUNCTURE OR BREAK THE BOTTOM SLABS OF MANHOLES AND SIMILAR STRUCTURE TO ALLOW DRAINAGE. BACKFILL AND COMPACT EXCAVATIONS RESULTING FROM REMOVAL OF UTILITY FACILITATES, AS REQUIRED TO RESTORE THE ORIGINAL GRADE.
- 6. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR THE ALTERATION AND ADJUSTMENTS OF NATURAL GAS, ELECTRIC, TELEPHONE AND ANY OTHER UTILITY BY THE UTILITY OWNER.

UTILITY NOTES (CONTINUED):

- 7. THE CONTRACTOR SHALL USE THE FOLLOWING PIPE MATERIALS (UNLESS OTHERWISE NOTED):
- SEWER PVC (POLYVINYL CHLORIDE), SDR 35
 DRAIN HDPE (HIGH DENSITY CORRUGATED POLYETHYLENE PIPE WITH SMOOTH
- DRAIN HDPE (HIGH DENSITY CORRUGATED POLYETHYLENE PIPE WITH SMOOTH INNER WALL), ASTM D2321 (UNLESS OTHERWISE SPECIFIED ON PLAN)
- DRAIN RCP CLASS IV (REINFORCED CONCRETE PIPE, WHERE SPECIFIED ON PLAN)
 WATER C.L.D.I. (CEMENT LINED DUCTILE IRON)
- 8. REFER TO DEMOLITION PLAN FOR EXISTING ITEMS TO BE REMOVED AND FOR UTILITY ABANDONMENT.
- BEFORE UTILITY WORK BEGINS, THE CONTRACTOR WILL COORDINATE WITH THE TOWN OF TOPSFIELD THE APPROPRIATE PERMIT AND INSPECTION FEES.
- ALL UTILITY CONNECTIONS THROUGH THE BUILDING WALL SHALL BE BY MEANS OF FLEXIBLE JOINTS.
- 11. ALL WATER GATES TO PROPOSED HYDRANTS ARE 6" DIAMETER UNLESS NOTED.
- 12. A MINIMUM OF 10 FEET CLEAR HORIZONTALLY SHALL BE MAINTAINED BETWEEN WATER MAINS AND SANITARY SEWER MAINS AND/OR STORM DRAINS. WHENEVER CONDITIONS PREVENT A LATERAL SEPARATION OF 10 FEET TO A WATER MAIN, THE WATER MAIN SHALL BE LAID IN A SEPARATE TRENCH AND THE DIFFERENCE IN ELEVATION BETWEEN THE WATER MAIN AND THE SEWER MAIN SHALL BE AT LEAST 18 INCHES.
- 13. ALL FILL MATERIAL IS TO BE IN PLACE, AND COMPACTED BEFORE INSTALLATION OF PROPOSED UTILITIES.
- 14. CONTRACTOR SHALL NOTIFY THE UTILITY AUTHORITY'S INSPECTORS 72 HOURS BEFORE CONNECTING TO ANY EXISTING LINE.
- 15. MINIMUM TRENCH WIDTH SHALL BE 2 FEET.
- 16. ALL WATER JOINTS ARE TO BE MECHANICAL JOINTS WITH THRUST BLOCKING AT BENDS.
- 17. CONTRACTOR SHALL MAINTAIN A MINIMUM OF 5'-0" COVER ON ALL WATERLINES AND A MAXIMUM OF 8'-0" COVER.
- 18. IN THE EVENT OF A VERTICAL CONFLICT BETWEEN WATERLINES, SANITARY LINES, STORM LINES AND GAS LINES (EXISTING AND PROPOSED), THE SANITARY LINE SHALL BE DUCTILE IRON PIPE WITH MECHANICAL JOINTS AT LEAST 10 FEET ON BOTH SIDES OF CROSSING, THE WATERLINE SHALL HAVE MECHANICAL JOINTS WITH APPROPRIATE THRUST BLOCKING AS REQUIRED TO PROVIDE A MINIMUM OF 18" CLEARANCE BETWEEN THE PIPES. WHERE THE WATERLINE IS LESS THAN THE 18" VERTICAL CLEARANCE AND MEETING 10' HORIZONTAL CLEARANCE CANNOT BE MET, THE WATER MUST BE ENCASED IN CONCRETE TO MEET THE REQUIREMENTS OF ANSI A21.10 OR ANSI 21.11 (AWWA C-151) (CLASS 50).
- 19. ALL CONCRETE FOR ENCASEMENTS SHALL HAVE A MINIMUM 28 DAY COMPRESSION STRENGTH OF 3000 P.S.I.
- 20. CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH THE SPECIFICATIONS OF THE LOCAL AUTHORITIES WITH REGARDS TO MATERIALS AND INSTALLATION OF THE WATER, SEWER, GAS AND ELECTRICAL AND TELECOMMUNICATIONS LINES.
- 21. ALL NECESSARY INSPECTIONS AND/OR CERTIFICATIONS REQUIRED BY CODES AND/OR UTILITY SERVICE COMPANIES SHALL BE PERFORMED PRIOR TO ANNOUNCED BUILDING POSSESSION AND THE FINAL CONNECTION OF SERVICE.
- 22. ALL HYDRANTS SHALL MEET LOCAL MUNICIPAL SPECIFICATION REQUIREMENTS AND SHALL BE INSTALLED IN ACCORDANCE WITH THE TOWN OF TOPSFIELD REQUIREMENTS.
- 23. DOMESTIC WATER SERVICES SHALL BE INSTALLED WITH APPROPRIATELY SIZED GATE, BOX, AND TEE FITTINGS.
- 24. ALL WATER MAIN APPURTENANCES, MATERIALS, METHODS OF INSTALLATION AND TESTING REQUIREMENTS SHALL MEET OR EXCEED THE TOWN OF TOPSFIELD REQUIREMENTS.
- 25. PRESSURE AND LEAKAGE TEST, DISINFECTION AND FLUSHING SHALL BE IN ACCORDANCE WITH ALL LOCAL AND MUNICIPAL STANDARDS AND REQUIREMENTS.
- 26. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS IN CONNECTION WITH THE UTILITY TESTS, FLUSHING AND INSPECTIONS AS REQUIRED BY THE LOCAL MUNICIPALITY.
- 27. SEWER PIPE BEDDING MATERIAL SHALL BE AS SPECIFIED ON THE DRAWINGS. IF LOCAL OR STATE AUTHORITIES REQUIRE DIFFERENT BEDDING OR BACKFILL MATERIAL, THEN THE MORE STRINGENT SHALL APPLY.
- 28. DRAWINGS DO NOT NECESSARILY SHOW ALL EXISTING UTILITIES.

PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC.

WILLIAMS

CIVIL

No.43119

REV DATE DESCRIPTION

APPLICANT\OWNER:

SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE ANDOVER, MA 01810

PROJECT:

RESIDENTIAL DEVELOPMENT 470 BOSTON STREET (ROUTE 1) TOPSFIELD, MA

PROJECT NO.	2165-01A	DATE:	10-13-2
SCALE:		DWG. NAME:	C-2165
DESIGNED BY:	DMR	CHECKED BY:	



civil & structural engineering • land surveying environmental consulting • landscape architecture www.allenmajor.com

10 MAIN STREET LAKEVILLE, MA 02347-1674 TEL: (508) 923-1010 FAX: (508) 923-6309

THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT.

CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD

COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.

SHEET No.

ABB-1

DRAWING TITLE:

ABBREVIATIONS & NOTES

Copyright©2016 Allen & Major Associates, Inc. All Rights Reserved

 $N:\PROJECTS\2165-01A\CIVIL\DRAWINGS\CURRENT\C-2165-01A$ - ABBREVIATIONS & NOTES.DWG

SIGNATURE

TOWN OF TOPSFIELD, MA

AND SPECIAL PERMIT

SITE PLAN AND SPECIAL PERMIT APPROVAL

SITE PLAN REVIEW

DATE

EROSION & SEDIMENTATION CONTROL NOTES:

- EROSION CONTROL SHALL BE INSTALLED PRIOR TO CONSTRUCTION AND SHALL BE ADEQUATE TO MAINTAIN SEDIMENT ON SITE. ANY MODIFICATIONS TO SILT CONTROLS SHOWN ON THE APPROVED PLANS AS A RESULT OF ACTUAL FIELD CONDITIONS OR CONSTRUCTION PRACTICES SHALL BE INSTALLED IN ACCORDANCE WITH B.M.P. (BEST MANAGEMENT PRACTICES) PER THE E.P.A. 2012 "CONSTRUCTION GENERAL PERMIT" MANUAL, AND MASSACHUSETTS 2003 EROSION & SEDIMENT CONTROL GUIDELINES FOR URBAN AND SUBURBAN AREAS, ANY SUCH MODIFICATIONS FROM THE ABOVE MANUALS SHALL BE INSTALLED AS APPROVED BY THE ENGINEER.
- AREAS OF EXPOSED SOIL UNDERGOING CONSTRUCTION THAT WILL NOT BE COVERED AND OR FINISHED GRADED SHALL BE STABILIZED AS SOON AS PRACTICABLE BUT IN NO CASE MORE THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY (UNLESS TOWN HAS STRICTER REQUIREMENTS WHICH SHALL BE FOLLOWED) IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. TEMPORARY EROSION CONTROL MEASURES SHALL INCLUDE EROSION CONTROL MESH, NETTING OR MULCH AS DIRECTED BY THE OWNER'S REPRESENTATIVE AND SHOWN ON THE DESIGN PLANS. IF MULCH IS USED, STRAW MULCH SHALL BE APPLIED AT THE RATE OF 4 BALES PER 1,000 SQUARE FEET. APPLICATION AREA SHALL BE SUFFICIENTLY COVERED WITH MULCH TO AVOID ANY VISIBLE SOIL EXPOSURE. MULCH SHALL BE KEPT MOIST TO AVOID LOSS DUE TO WIND. MULCH AND NETTING SHALL BE APPLIED IN THE BASE OF ALL GRASSED WATERWAYS, IN VEGETATIVE SLOPES WHICH EXCEED 15% AND DISTURBED AREAS WITHIN 100 FEET OF WETLANDS OR STREAMS.
- 3. IF DISTURBED AREAS DO NOT RECEIVE FINAL SEEDING BY OCTOBER 1ST OF THE CONSTRUCTION YEAR, THEN ALL DISTURBED AREAS SHALL BE SEEDED WITH A WINTER COVER CROP AT THE RATE OF 3 LBS PER 1,000 SQUARE FEET. WINTER SEEDING SHALL BE COVERED WITH EROSION CONTROL MESH (MULCH AND NETTING). HEAVY GRADE MATS SHALL BE USED IN THE BASE OF ALL GRASSED WATERWAYS ON VEGETATED SLOPES IN EXCESS OF 15%, AND ANY DISTURBED AREAS WITHIN 100 FEET OF WETLANDS OR STREAMS. MULCH AND NETTING SHALL ALSO BE PROVIDED FOR ADDITIONAL WINTER PROTECTION.
- 4. ALL TOPSOIL SHALL BE COLLECTED, STOCKPILED, SEEDED WITH RYE AT 3LBS PER 1,000 SQUARE FOOT AND MULCHED, AND REUSED AS REQUIRED. SILTATION FENCING SHALL BE PLACED DOWN GRADIENT FROM STOCKPILED LOAM. LOAM SHALL BE STOCKPILED AT LOCATIONS DESIGNATED BY THE OWNER AND ENGINEER.
- ALL FILTER BARRIERS, SILT SACKS, AND EROSION CONTROL BERMS SHALL BE INSTALLED ACCORDING TO THE EROSION CONTROL PLAN. THESE SHALL BE MAINTAINED DURING DEVELOPMENT TO REMOVE SEDIMENT FROM RUNOFF WATER. ALL THE FILTER BARRIERS AND EROSION CONTROL BERMS SHALL BE INSPECTED AFTER ANY RAINFALL OR RUNOFF EVENT, MAINTAINED AND CLEANED UNTIL ALL AREAS HAVE AT LEAST 85-90% VIGOROUS PERENNIAL COVER OF GRASSES.
- ADJACENT ROADS SHALL BE PERIODICALLY SWEPT OR WASHED TO AVOID TRACKING MUD, DUST OR DEBRIS FROM THE CONSTRUCTION AREA AS OFTEN AS NECESSARY (WHICH COULD BE ON A DAILY BASIS) TO REMOVE ANY SOIL OR SEDIMENTS AT NO ADDITIONAL COST TO THE OWNER. A WATERING TRUCK WILL BE USED TO PERIODICALLY SPRINKLE CONSTRUCTION AREAS IN ORDER TO KEEP THE LEVEL OF DUST TO A MINIMUM DURING THE DRY MONTHS AT NO ADDITIONAL COST TO THE OWNER.
- THE CONTRACTOR SHALL USE EXTREME CAUTION TO AVOID ALLOWING SEDIMENTS TO ENTER THE STORM DRAIN SYSTEM DURING CONSTRUCTION. BOTH EXISTING AND PROPOSED CATCH BASIN INLETS SHALL BE PROTECTED DURING CONSTRUCTION BY THE USE SILT SACKS AND OR STRAW BALE BARRIERS AROUND EACH INLET AS NOTED ON THE PLANS. INLET PROTECTION MAY BE REMOVED ONLY AFTER FINISHED AREAS ARE PAVED AND THE VEGETATED SLOPES ARE ESTABLISHED WITH AT LEAST 85-90% OF VIGOROUS PERENNIAL GROWTH.
- AS APPLICABLE, EROSION CONTROL MESH SHALL BE APPLIED IN ACCORDANCE WITH THE PLANS OVER ALL FINISHED SEEDED AREAS AS SPECIFIED ON THE DESIGN PLANS.
- 9. AT A MINIMUM, ALL STRAW BALES, SILT FENCE AND FILTER FABRIC SHALL REMAIN IN PLACE UNTIL SEEDINGS OR PLANTINGS HAVE BECOME 85-90% ESTABLISHED. THE TOWN OF TOPSFIELD CONSERVATION COMMISSION MUST APPROVE THE REMOVAL OR RELOCATION OF ANY OF THE STRAW BALES AND FILTER FABRIC. ONCE THE STRAWBALES AND SILT FENCE IS REMOVED THE AREAS ARE TO BE LOAM AND SEEDED TO ACHIEVE FULL STABILIZATION.
- 10. AT THE OWNER'S DISCRETION ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED TO MAINTAIN STABILITY OF EARTHWORKS AND FINISHED GRADED AREAS. THE CONTRACTOR, AT HIS EXPENSE, WILL BE RESPONSIBLE FOR PROVIDING AND INSTALLING ANY ADDITIONAL MEASURES AS SPECIFIED BY THE OWNER. THIS INCLUDES BUT IS NOT LIMITED TO REQUESTS BY MA DEP. THE ENGINEER AND THE MUNICIPALITY, AS AUTHORIZED BY THE OWNER. FAILURE TO COMPLY WITH THE OWNER'S DIRECTIONS WILL RESULT IN DISCONTINUATION OF CONSTRUCTION ACTIVITIES.
- 11. INSPECTIONS AND MONITORING MAINTENANCE MEASURES SHALL BE APPLIED AS NEEDED DURING THE ENTIRE CONSTRUCTION CYCLE. WEEKLY INSPECTIONS SHALL BE HELD THROUGH THE DURATION OF CONSTRUCTION ACTIVITY. WEEKLY INSPECTION REPORTS SHALL BE MAINTAINED BY THE CONTRACTOR AND LOCATED IN THE CONTRACTORS FIELD OFFICE ONSITE. IN ADDITION TO THE NORMAL WEEKLY INSPECTIONS, THE CONTRACTOR SHALL PERFORM AN INSPECTION OF ALL EROSION CONTROL MEASURES AFTER EACH RAINFALL OR RUNOFF EVENT, AND PERFORM THE NECESSARY REPAIRS. THE INSPECTIONS SHALL INCLUDE BUT NOT BE LIMITED TO THE SITE'S DOWN STREAM DISCHARGE POINTS.
- 12. IF ANY EVIDENCE OF SEDIMENTATION IS OBSERVED AT THE STORMWATER MANAGEMENT AREA INLETS, THE CONTRACTOR SHALL, AT HIS OWN EXPENSE, PROVIDE A PLAN TO THE ENGINEER TO REMOVE ANY ACCUMULATED SEDIMENT IN THESE AREAS. THE CONTRACTOR SHALL ALSO IMMEDIATELY PROVIDE ADDITIONAL ON SITE EROSION AND SEDIMENTATION CONTROL MEASURES TO PREVENT FURTHER DEGRADATION OF THE AREA.
- 13. FOLLOWING THE TEMPORARY OR FINAL SEEDINGS, THE CONTRACTOR SHALL INSPECT THE WORK AREA SEMI-MONTHLY TO ENSURE THE AREAS HAVE A MINIMUM OF 85-90% VEGETATED VIGOROUS GROWTH. RE-SEEDING SHALL BE CARRIED OUT BY THE CONTRACTOR WITH FOLLOW UP INSPECTIONS IN THE EVENT OF ANY FAILURES UNTIL VEGETATION IS ADEQUATELY ESTABLISHED.
- 14. CONTRACTOR & ALL SITE SUBCONTRACTORS SHALL BE FAMILIAR WITH & FOLLOW ALL APPROVED PERMITS AND CONDITIONS. CONTRACTOR SHALL MAINTAIN A COPY OF ALL APPROVED PERMITS ONSITE, INCLUDING THE ORDER OF CONDITIONS FROM THE TOPSFIELD CONSERVATION COMMISSION. ALL CONDITIONS & RECOMMENDATIONS WITHIN THE APPROVED PERMITS SHALL BE COMPLETED.
- 15. ALL EROSION MEASURES SHALL BE INSTALLED PRIOR TO CONSTRUCTION AND SHALL BE ADEQUATE TO MAINTAIN SEDIMENT ON SITE. ANY MODIFICATIONS SHALL BE INSTALLED AS DIRECTED BY THE ENGINEER OR THE TOWN OF TOPSFIELD.
- 16. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE MAINTAINED DURING CONSTRUCTION, AND SHALL REMAIN IN PLACE UNTIL ALL SITE WORK IS COMPLETE AND GROUND COVER IS ESTABLISHED.
- 17. TOP OF STOCKPILES SHALL BE COVERED IN SUCH MANNER THAT STORMWATER DOES NOT INFILTRATE THE MATERIALS AND THEREBY RENDER THE SAME UNSUITABLE FOR FILL USE.

EROSION & SEDIMENTATION CONTROL NOTES (CONTINUED):

- 18. ALL DISTURBED OR EXPOSED AREAS SUBJECT TO EROSION SHALL BE STABILIZED WITH MULCH OR SEEDED FOR TEMPORARY VEGETATIVE COVER. NO AREA, SUBJECT TO EROSION SHALL BE LEFT DISTURBED AND UNSTABILIZED FOR PERIODS LONGER THAN IS ABSOLUTELY NECESSARY TO CARRY OUT THAT PORTION OF THE CONSTRUCTION WORK OR SIX MONTHS AFTER SOIL HAS BEEN DISTURBED WHICHEVER IS LESS.
- 19. CULVERT/PIPE INLETS AND OUTFALLS SHALL BE PROTECTED BY STRAW BALE FILTERS AND STONE CHECK DAMS UNTIL DISTURBED AREAS ARE PERMANENTLY STABILIZED.
- 20. STRAW BALE DIKES SHALL BE CONSTRUCTED AT ALL EXISTING & PROPOSED CATCH BASINS. NO SEDIMENTATION SHALL ENTER THE ON-SITE OR OFF-SITE DRAINAGE SYSTEMS AT ANY TIME.
- 21. ALL EROSION CONTROL MEASURES SHALL BE ROUTINELY INSPECTED, CLEANED AND REPAIRED OR REPLACED AS NECESSARY THROUGHOUT ALL PHASES OF CONSTRUCTION. IN ADDITION, INSPECTION SHALL TAKE PLACE WEEKLY AND BEFORE AND AFTER EACH RAINFALL EVENT.
- 22. ALL PROPOSED SLOPES EQUAL TO OR GREATER THAN 3:1 SHALL BE STABILIZED WITH JUTE MESH AND PROTECTED FROM EROSION UNTIL WORK IS COMPLETE AND GROUND COVER IS ESTABLISHED.
- 23. THE CONTRACTOR SHALL KEEP ON SITE AT ALL TIMES ADDITIONAL STRAW BALES AND EXTRA SILTATION FENCING FOR INSTALLATION AT THE DIRECTION OF THE ENGINEER OR THE TOWN ENGINEER TO MITIGATE ANY EMERGENCY CONDITION.
- 24. AS CONSTRUCTION DISTURBANCE IS GREATER THAN 1 ACRE. A NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) CONSTRUCTION GENERAL PERMIT NOI, AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP) WILL NEED TO BE SUBMITTED TO THE EPA. THE NPDES PERMIT FOR STORM WATER DISCHARGE, & CONSTRUCTION GENERAL PERMIT NOI WILL BE REQUIRED TO BE SUBMITTED AT LEAST 14 DAYS PRIOR TO COMMENCING CONSTRUCTION BY THE CONTRACTOR.
- 25. OWNER AND CONTRACTOR ARE RESPONSIBLE FOR COMPLIANCE WITH THE CONSTRUCTION GENERAL PERMIT NOI. WEEKLY SWPPP INSPECTION REPORTS TO BE PERFORMED BY CONTRACTOR. COPIES OF ALL SWPPP INSPECTION REPORTS SHALL BE PROVIDED TO THE TOWN OF TOPSFIELD, EPA, DEP, OR ANY OTHER AUTHORITY REQUESTING WITHIN 3 DAYS OF EACH INSPECTION.
- 26. APPLICABLE WORK AND MATERIALS SHALL COMPLY WITH ALL TOWN OF TOPSFIELD, MA DEP. EPA CONSTRUCTION GENERAL PERMIT STANDARDS. ALL CONSTRUCTION SHALL CONFORM TO THE APPLICABLE SITE PLAN REGULATIONS FROM THE TOWN OF TOPSFIELD AND USDA SOIL CONSERVATION SERVICE VEGETATIVE PRACTICES IN SITE DEVELOPMENT.
- 27. A WATERING TRUCK SHALL BE USED TO PERIODICALLY SPRINKLE CONSTRUCTION AREAS IN ORDER TO KEEP THE LEVEL OF DUST TO A MINIMUM DURING THE DRY MONTHS AND AS REQUIRED.
- 28. IF DEWATERING IS NECESSARY IT SHALL ONLY BE COMPLETED AS FOLLOWS: THE DISCHARGE SHALL BE STOPPED IMMEDIATELY IF THE RECEIVING AREA SHOWS ANY SIGN OF INSTABILITY OR EROSION. ALL CHANNELS, SWALES, AND DITCHES DUG FOR DISCHARGING WATER FROM THE EXCAVATED AREA SHALL BE STABLE PRIOR TO DIRECTING DISCHARGE TO THEM. IF A CONSTRUCTION EQUIPMENT BUCKET IS USED, IT SHALL EMPTY THE MATERIAL TO A STABLE AREA. NO DEWATERING SHALL OCCUR DURING PERIODS OF INTENSE, HEAVY RAIN. FLOW TO THE SEDIMENT REMOVAL STRUCTURE SHALL NOT EXCEED THE STRUCTURES CAPACITY TO SETTLE AND FILTER FLOW OR IS VOLUME CAPACITY. WHENEVER POSSIBLE, THE DISCHARGE FROM THE SEDIMENT REMOVAL STRUCTURE SHALL DRAIN TO A WELL-VEGETATED BUFFER BY SHEET FLOW WHILE MAXIMIZING THE DISTANCE TO THE NEAREST WATER RESOURCE AND MINIMIZING THE SLOPE OF THE BUFFER AREA. THERE SHALL BE NO DIRECT DISCHARGE TO EXISTING WETLANDS OR STREAMS. ALL DISCHARGE SHALL BE IN COMPLIANCE WITH STATE, LOCAL, AND FEDERAL REQUIREMENTS.
- 29. INITIATE STABILIZATION IMMEDIATELY IF CONSTRUCTION WORK TEMPORARILY OR PERMANENTLY CEASES.
- 30. ALL DISCHARGES FROM POLLUTION SOURCES IS PROHIBITED ONSITE SUCH AS FUELS, WASTEWATER FROM WASH OUT OF CONCRETE, WASTEWATER FROM CLEAN OUT OF PAINTS. FORM RELEASE OILS, SOLVENTS, ADHESIVES, CURING COMPOUNDS, POLLUTANTS USED FOR MAINTENANCE OF VEHICLES AND EQUIPMENT, SOAPS & SOLVENTS, TOXIC OR HAZARDOUS SUBSTANCES, CHEMICALS AND OILS. IF A POLLUTANT IS DISCHARGED IT NEEDS TO BE IMMEDIATELY CLEANED UP BY REMOVING THE CHEMICAL AND AFFECTED SOIL OR AREA OF SPILL FROM THE SITE IN ACCORDANCE WITH BOTH THE MANUFACTURER RECOMMENDATIONS, FEDERAL, STATE, AND LOCAL REQUIREMENTS. DO NOT HOSE DOWN AND SPREAD SPILLED ITEM. ALL CHEMICALS USED ON THE SITE SHALL BE IN LEAK-PROOF CONTAINERS STORED AWAY FROM WETLANDS, SURFACE WATERS, STORMWATER INLETS, AND DRAINAGE MEASURES. SPILL KITS SHALL BE AVAILABLE ONSITE FOR EMERGENCY USE. THERE SHALL BE A SECONDARY CONTAINMENT MEASURE OF ALL CHEMICALS IN ADDITION TO SPILL-PROOF CONTAINERS.
- 31. PRIOR TO COMMENCEMENT OF CONSTRUCTION, APPLICABLE CONTRACTOR PERSONNEL MUST HAVE AN UNDERSTANDING OF THE EPA CONSTRUCTION GENERAL PERMIT REQUIREMENTS AND THEIR SPECIFIC RESPONSIBILITIES UNDER THE PERMIT. AT A MINIMUM, PERSONNEL MUST BE TRAINED AND UNDERSTAND THE FOLLOWING: LOCATION OF ALL STORMWATER CONTROLS AND HOW TO MAINTAIN THEM, PROCEDURES FOR COMPLYING WITH THE POLLUTION PREVENTION REQUIREMENTS. PROCEDURES FOR CONDUCTING INSPECTIONS, RECORDING FINDINGS, AND TAKING CORRECTIVE ACTION.
- 32. ALL SEDIMENT TRACKED ONTO ROADWAYS MUST BE REMOVED AT END OF EACH WORK
- 33. ALL USE OF CATIONIC TREATMENT CHEMICALS (EXAMPLES INCLUDE POLYMERS, CHITOSAN, CATIONIC PAM, FLOCCULANTS OR OTHER CHEMICAL UTILIZED FOR STABILIZATION) ARE PROHIBITED. IF ALL OTHER AVAILABLE STABILIZATION MEASURES ARE NOT POSSIBLE AND USE OF CATIONIC CHEMICALS IS ABSOLUTELY NECESSARY THE CONTRACTOR WILL NEED TO CONTACT THE EPA NEW ENGLAND OFFICE IN WRITING FOR APPROVAL AND SPECIFIC REQUIREMENTS (MAXIMUM DOSAGE RATE, RESIDUAL TESTING, SPECIFIC LIMITATIONS, ETC) PRIOR TO USE.
- 34. IF USING NON-VEGETATIVE STABILIZATION MEASURES, IT MUST BE COMPLETED NO LATER THAN 14 DAYS AFTER INITIATING STABILIZATION. ALL AREAS OF EXPOSED SOILS MUST BE COVERED.
- 35. INSPECTIONS OF EROSION CONTROL MEASURES SHALL BE AT LEAST ONCE EVERY 7 DAYS BY THE CONTRACTOR. AT A MINIMUM INSPECTIONS SHALL INCLUDE ALL DISTURBED AREAS, ALL STORMWATER CONTROLS AND POLLUTION PREVENTION MEASURES, ALL LOCATIONS WHERE STABILIZATION MEASURES HAVE BEEN IMPLEMENTED, EQUIPMENT AND MATERIAL STORAGE AREAS, ALL AREAS WHERE STORMWATER FLOWS AND ALL POINTS OF DISCHARGE. WHEN CORRECTIVE ACTIONS ARE REQUIRED, THE CONTRACTOR MUST IMMEDIATELY TAKE ALL STEPS TO PREVENT POLLUTANT DISCHARGES UNTIL A PERMANENT SOLUTION IS IMPLEMENTED. AS NECESSARY NEW OR MODIFIED CONTROLS MUST BE INSTALLED AND OPERATIONAL, THE REPAIR MUST BE COMPLETED WITHIN 7 DAYS FROM THE TIME OF DISCOVERY. WITHIN 24 HOURS OF A TRIGGERING CONDITION OCCURRING THAT REQUIRES A CORRECTIVE ACTION, A CORRECTIVE ACTION REPORT MUST BE COMPLETED.

MAINTENANCE:

ALL MEASURES STATED ON THE STORMWATER POLLUTION PREVENTION PLANS, SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION BY CONTRACTOR UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON IN ACCORDANCE WITH THE CONTRACT DOCUMENTS OR THE APPLICABLE PERMIT, WHICHEVER IS MORE STRINGENT, AND REPAIRED IN ACCORDANCE WITH THE FOLLOWING:

- 1. INLET PROTECTION DEVICES AND BARRIERS SHALL BE REPAIRED OR REPLACED IF THEY SHOW SIGNS OF UNDERMINING, OR DETERIORATION.
- 2. ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A HEALTHY STAND OF GRASS IS MAINTAINED. AREAS SHOULD BE FERTILIZED, WATERED, AND RESEEDED AS
- 3. ALL SEDIMENT CONTROLS SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE TUBULAR SEDIMENT CONTROLS WHEN IT REACHES HALF THE HEIGHT OF THE CONTROL MEASURE OR AS REQUESTED BY THE OWNER OR ENGINEER.
- 4. THE CONSTRUCTION ENTRANCES SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE CONSTRUCTION ENTRANCES AS CONDITIONS DEMAND.
- 5. THE TEMPORARY PARKING AND STORAGE AREA SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE). THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE TEMPORARY PARKING AS CONDITIONS DEMAND.
- OUTLET STRUCTURES IN THE SEDIMENTATION BASINS SHALL BE MAINTAINED IN OPERATIONAL CONDITIONS AT ALL TIMES. SEDIMENT SHALL BE REMOVED FROM SEDIMENT BASINS OR TRAPS WHEN THE DESIGN CAPACITY HAS BEEN REDUCED BY 50%.

ABBREVIATIONS:

INVERT, INVERT ELEVATION

INV, I.E.

ABAN ADA ADJ	ABANDON AMERICANS WITH DISABILITIES ACTS ADJUST		
B BC BIT BLDG BM BOS BOW BV&B BVW	BORING BOTTOM OF CURB BITUMINOUS BUILDING BENCH MARK BOTTOM OF SLOPE BOTTOM OF WALL BUTTERFLY VALVE & BOX BORDERING VEGETATED WETLAND	L LP MAT MAX MH MIN	LENGTH LIGHT POLE MATERIAL MAXIMUM MANHOLE MINIMUM
CATV CB CF CFS CI CL CLDI CLF CMP CO CONC CONST	CABLE TELEVISION CATCH BASIN CUBIC FEET CUBIC FEET PER SECOND CAST IRON (PIPE) CENTERLINE CEMENT LINED DUCTILE IRON (PIPE) CHAIN LINK FENCE CORRUGATED METAL PIPE CLEAN OUT CONCRETE CONSTRUCTION	MISC MTD MW N NIC NO NTS OC OD OHW OVHD OW	MISCELLANEOUS MOUNTED MONITORING WELL NORTH NOT IN CONTRACT NUMBER NOT TO SCALE ON CENTER OUTSIDE DIAMETER OVERHEAD WIRE OVERHEAD OBSERVATION WELL
CONT CRD CUL CY	CONTRACTOR COORDINATE CULVERT CUBIC YARD	PC PCC PI PL POC	POINT OF CURVATURE PRECAST CONCRETE CURB POINT OF INTERSECTION PROPERTY LINE POINT ON CURVATURE
DB DBL DEM DET DIA DI DIM DMH	DISTRIBUTION BOX DOUBLE DEMOLISH DETENTION DIAMETER DUCTILE IRON (PIPE) DIMENSION DRAIN MANHOLE	POT PRC PROP, P PT PVC	POINT ON TANGENT POINT OF REVERSE CURVATURE
DW DWG DYCL EHH EL ELEC EMH EOP	DOMESTIC WATER (OR DRY WELL) DRAWING DOUBLE YELLOW CENTERLINE ELECTRIC HANDHOLE ELECTRIC ELECTRIC ELECTRIC MANHOLE EDGE OF PAVEMENT	R&S RCP RD RELOC REM RET ROW RR RWY	REMOVE & STACK REINFORCED CONCRETE PIPE ROAD (OR ROOF DRAIN) RELOCATE REMOVE RETAIN, RETAINING OR RETENTION
EOR EOW ETC EXIST EXT FCC FES FFE FPS FS FT	EDGE OF ROAD EDGE OF WETLANDS ELECTRIC, TELEPHONE, CABLE EXISTING EXTERIOR FLUSH CONCRETE CURB FLARED END SECTION FINISH FLOOR ELEVATION FEET PER SECOND FIRE SERVICE FOOT/FEET	SD SF SGC SMH SP SPEC STA STD SWEL SWEL SWLL SYCL	
GC GEN GG GR GRAN GV GV&B GW	GENERAL CONTRACTOR GENERAL GAS GATE GUIDE RAIL GRANITE GATE VALVE GATE VALVE & BOX GROUND WATER	TB TC TD TEL, T TMH TOS TOW TP TYP	TEST BORING TOP OF CURB TRENCH DRAIN TELEPHONE TELEPHONE MANHOLE TOP OF SLOPE TOP OF WALL TEST PIT TYPICAL
H HOR HT HW	HORIZONTAL HORIZONTAL HEIGHT HEADWALL	UD UP	UNDERDRAIN UTILITY POLE
HWY HYD	HIGHWAY HYDRANT INSIDE DIAMETER	V VCP VERT VGC	VERTICAL VITRIFIED CLAY PIPE VERTICAL VERTICAL GRANITE CURB
IN INCL INST	INCHES INCLUDE INSTALLED	WG WM WMH	WATER GATE WATER MANHOLE

WATER MANHOLE WATER SHUTOFF

CONSTRUCTION GENERAL PERMIT NOTES AND NARRATIVE:

NARRATIVE: THE STORMWATER POLLUTION PREVENTION PLANS CONSIST OF THE EROSION CONTROL PLANS TOGETHER WITH AN EXISTING CONDITIONS PLANS, GRADING PLANS, ABBREVIATIONS AND NOTES SHEETS, AND DETAIL SHEETS.

THE EROSION CONTROL PLAN WILL BE IMPLEMENTED TO:

- A. TREAT EROSION AS SOON AS POSSIBLE AFTER DISTURBANCE.
- B. PREVENT SEDIMENT FROM LEAVING THE CONSTRUCTION AREA AND ENTERING THE RECEIVING WATERS.
- C. CONSTRUCTION ACTIVITIES SHALL BE SCHEDULED TO MINIMIZE EROSION.
- D. ONLY DISTURB, CLEAR, OR GRADE AREAS NECESSARY FOR

TOWN OF TOPSFIELD, MA SITE PLAN REVIEW

	-
SIGNATURE	DATE

AND SPECIAL PERMIT

WILLIAMS CIVIL

PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC.

DATE DESCRIPTION

SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE ANDOVER, MA 01810

PROJECT:

APPLICANT\OWNER:

RESIDENTIAL DEVELOPMENT 470 BOSTON STREET (ROUTE 1) TOPSFIELD, MA

PROJECT NO.	2165-01A	DATE:	10-13-20
SCALE:	NONE	DWG. NAME:	C-2165-0
DESIGNED BY:	DMR	CHECKED BY:	

ERMITTING

ASSOCIATES, INC. civil & structural engineering + land surveying environmental consulting + landscape architecture

> www.allenmajor.com 10 MAIN STREET LAKEVILLE, MA 02347-1674 TEL: (508) 923-1010

FAX: (508) 923-6309 WOBURN, MA ♦ LAKEVILLE, MA ♦ MANCHESTER, NI

THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.

SHEET No.

ABB-2

DRAWING TITLE:

ABBREVIATIONS & NOTES

Copyright@2016 Allen & Major Associates, Inc.

N:\PROJECTS\2165-01A\CIVIL\DRAWINGS\CURRENT\C-2165-01A - ABBREVIATIONS & NOTES.DWG

STORMWATER POLLUTION PREVENTION PLAN

2.1 GENERAL

FOR GRADING AND DRAINAGE SEE DRAWING SHEETS C-3A & C-3B

2.1.1. THE FIRST STAGE INVOLVES ACTIVITIES NEEDED TO ADDRESS STORMWATER MANAGEMENT; EXCAVATING MATERIAL DESIGNATED FOR OFF-SITE REMOVAL OR ON-SITE RELOCATION; AND FENCING SELECTED AREAS. STAGE ONE WILL PREPARE SITE FOR CONVENTIONAL CONSTRUCTION.

2.1.2. THE SECOND STAGE WILL CONSIST OF ROUTINE CONSTRUCTION INVOLVING DEMOLITION, PAVING. LANDSCAPING AND UTILITIES.

2.1.3. THERE ARE GENERAL PHASES OF CONSTRUCTION AS IDENTIFIED BELOW. IN EACH PHASE OF CONSTRUCTION, IMPLEMENT STANDARD EROSION AND SEDIMENT CONTROL PRACTICES PRIOR TO INITIATING EARTH DISTURBING ACTIVITIES, AND MAINTAIN THESE PRACTICES THROUGHOUT THE COURSE OF CONSTRUCTION.

TYPICAL PRACTICES TO BE APPLIED TO THE SITE INCLUDE THE FOLLOWING:

PRIOR TO DEMOLITION AND EARTH DISTURBANCE IN ANY WORK AREA, INSTALL SILTATION BARRIERS (BALES OR SILT FENCE WITH BALES) BETWEEN THE WORK AREA AND THE AREA(S) TO WHICH IT DRAINS.

DISCHARGE WATER FROM DEWATERING OPERATIONS TO A TEMPORARY SILTATION TRAP OR SEDIMENTATION BASIN.

PROVIDE TEMPORARY BERMS AND SWALES TO DIVERT SURFACE WATER AWAY FROM THE AREAS THAT WILL BE EXPOSED BY CONSTRUCTION ACTIVITY TO MINIMIZE THE AMOUNT OF SURFACE WATER COMING INTO CONTACT WITH EXPOSED SOILS. PROVIDE STABLE OUTLETS FOR THESE DEVICES, AND LINE OR VEGETATE THESE DIVERSIONS TO PROVIDE FOR DEVICES, AND LINE OR VEGETATE THESE DIVERSIONS TO PROVIDE FOR THEIR STABILITY DURING CONSTRUCTION.

LIMIT THE EXTENT OF EXPOSED SOILS TO AREAS THAT CAN BE WORKED AND RESTABILIZED WITHIN THE CONSTRUCTION SEASON AND DURING THE SPECIFIC CONSTRUCTION PHASE. WHEN EARTHWORK CONSTRUCTION ACTIVITY IN AN AREA IS COMPLETE, STABILIZE THE AREA WITH A SUITABLE SURFACE AS DESCRIBED BELOW.

IN ADDITION TO THESE PRACTICES, FOLLOW THE SPECIAL PRACTICES DESCRIBED BELOW. COMPLY WITH THE DIRECTIONS OF THE OWNER'S REPRESENTATIVE TO ADDRESS EROSION AND SEDIMENTATION CONDITIONS THAT MAY ARISE ON A CASE BY CASE BASIS DURING CONSTRUCTION.

THE FOLLOWING IS A DESCRIPTION OF MINIMUM CONSTRUCTION REQUIREMENTS AND DOES NOT RELIEVE THE CONTRACTOR OF HIS RESPONSIBILITIES WITH REGARD TO DETERMINING THE ADEQUACY OF MEANS AND METHODS OF CONSTRUCTION.

2.2 ESTIMATED CONSTRUCTION SEQUENCING.

THE FOLLOWING IS AN ESTIMATED CONSTRUCTION SEQUENCING. SOME ACTIVITIES MAY OCCUR AT THE SAME TIME RATHER THAN AT SEPARATE TIMES OR OUT OF SEQUENCE DUE TO ACTUAL FIELD CONDITIONS OR OTHER FACTORS. ACTUAL SCHEDULING WILL BE COMPLETED BY THE SITE CONTRACTOR. (CONTRACTOR TO FOLLOW ANY ADDITIONAL PERMIT REQUIREMENTS OR STEPS AT NO ADDITIONAL COST TO

THE OWNERS FROM EITHER STATE OR LOCAL PERMITS, THIS INCLUDES BUT IS NOT LIMITED TO THE ORDER OF CONDITIONS FROM THE TOPSFIELD CONSERVATION COMMISSION)

- INSTALL ALL EROSION CONTROL MEASURES INCLUDING BUT NOT LIMITED TO TEMPORARY STRAW BALE FILTERS, SILT SACKS, CONSTRUCTION ENTRANCES, AND STRAWBALES AND SILT FENCE.
- SETUP STAGING AND MATERIAL STORAGE / STOCKPILE AREAS.
- IF REQUIRED, CONSTRUCT TEMPORARY SILT / DEWATERING BASINS.
- PROTECT AND MARK ALL EXISTING ITEMS NOTED TO REMAIN.
- PERFORM DEMOLITION WORK. SURVEY AND IDENTIFY LIMITS OF SITE CLEARING. CONDUCT SITE CLEARING.
- PULVERIZE EXISTING PAVEMENT TO BE REMOVED AND DEMO EXISTING BUILDING SECTIONS AND MATERIALS AS NOTED.
- REMOVE EXISTING LOAM AND SUBSOIL AND STOCKPILE FOR REUSE.
- PERFORM ROUGH GRADING.
- INSTALL UNDERGROUND UTILITIES.
- PERFORM FINE GRADING; PLACE BINDER PAVEMENT COURSE.
- PLACE PAVEMENT TOP COURSE; CONSTRUCT SIDEWALKS AND ALL OTHER SITE IMPROVEMENTS.
- ERADICATE EXISTING PAVEMENT MARKINGS ON REMAINING PAVEMENT.
- INSTALL NEW PAVEMENT MARKINGS, SITE SIGNAGE & COMPLETE LANDSCAPING.
- REMOVE TEMPORARY SILT CONTROLS AFTER ONCE GIVEN APPROVAL BY TOPSFIELD CONSERVATION COMMISSION AND SITE IS STABILIZED.

OPERATION AND MAINTENANCE CONSTRUCTION ACTIVITIES:

- CONTACT THE TOPSFIELD CONSERVATION COMMISSION AGENT AT LEAST THREE (3) DAYS PRIOR TO START OF CONSTRUCTION.
- 2. INSTALL STRAWBALES AND SILT FENCE AS SHOWN ON THE EROSION CONTROL PLAN. INSTALL CONSTRUCTION FENCING IF DETERMINED TO BE NECESSARY AT THE COMMENCEMENT OF CONSTRUCTION.
- INSTALL THE CONSTRUCTION ENTRANCES AT THE LOCATIONS SHOWN ON THE EROSION AND CONTROL PLAN.
- 4. SITE ACCESS SHALL BE ACHIEVED ONLY FROM THE DESIGNATED CONSTRUCTION ENTRANCES.
- STOCKPILES SHALL BE STABILIZED WITH EROSION CONTROL MATTING OR TEMPORARY SEEDING WHENEVER PRACTICABLE, BUT IN NO CASE MORE THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.
- 6. INSTALL SILT SACKS AND STRAWBALES AROUND EACH DRAIN INLET AS SOON AS PRACTICABLE.
- 7. ALL EROSION CONTROL MEASURES SHALL BE INSPECTED WEEKLY AND AFTER EVERY RAINFALL EVENT.
- 8. ALL EROSION CONTROL MEASURES SHALL BE MAINTAINED, REPAIRED OR REPLACED AS REQUIRED OR AT THE DIRECTION OF THE OWNER'S ENGINEER. THE TOWN ENGINEER. OR THE TOWN CONSERVATION AGENT.
- SEDIMENT ACCUMULATION UP-GRADIENT OF THE STRAWBALES AND SILT FENCE GREATER THAN 6" IN DEPTH SHALL BE REMOVED AND DISPOSED OF IN ACCORDANCE WITH ALL APPLICABLE REGULATIONS.
- 10. IF IT APPEARS THAT SEDIMENT IS EXITING THE SITE, SILT SACKS SHALL BE INSTALLED IN ALL CATCH BASINS ADJACENT TO THE SITE. SEDIMENT ACCUMULATION ON ALL ADJACENT CATCH BASIN INLETS SHALL BE REMOVED AND THE SILT SACK REPLACED IF TORN OR DAMAGED.
- 11. INSTALL STONE OR DIVERSION SWALE STRAW BALE CHECK DAMS ON SITE AS REQUIRED DURING CONSTRUCTION. REFER TO THE EROSION CONTROL DRAWING, DETAIL SHEETS D-1 THRU D-8.
- 12. THE CONTRACTOR SHALL COMPLY WITH THE GENERAL AND EROSION NOTES AS SHOWN ON THE SITE DEVELOPMENT PLANS AND SPECIFICATIONS.
- 13. THE STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSPECTED WEEKLY. THE ENTRANCES SHALL BE MAINTAINED BY ADDING ADDITIONAL CLEAN, ANGULAR, DURABLE STONE TO REMOVE THE SOIL FROM THE CONSTRUCTION VEHICLE TIRES WHEN EXITING THE SITE. IF SOIL IS STILL LEAVING THE SITE VIA THE CONSTRUCTION VEHICLE TIRES, ADJACENT ROADWAYS SHALL BE KEPT CLEAN BY STREET SWEEPING.
- 14. DUST POLLUTION SHALL BE CONTROLLED USING ON-SITE WATER TRUCKS AND OR AN APPROVED SOIL STABILIZATION PRODUCT.
- 15. CARE SHOULD BE TAKEN TO PREVENT DISCHARGE OF SEDIMENT TO ABUTTERS.

2.3 MAINTENANCE

- 2.3.1 DURING THE PERIOD OF CONSTRUCTION AND/OR UNTIL LONG TERM VEGETATION IS ESTABLISHED: SEEDED AREAS WILL BE FERTILIZED AND RESEEDED AS NECESSARY TO INSURE VEGETATION ESTABLISHMENT
- TEMPORARY SEDIMENTATION BASINS WILL BE CHECKED AFTER EACH SIGNIFICANT RAINFALL AND NO LESS THAN WEEKLY, AND CLEANED AS NEEDED TO RETAIN STORAGE CAPACITY.
- TEMPORARY DRAINAGE SWALES WILL BE CHECKED WEEKLY AND REPAIRED WHEN NECESSARY.
- THE HAYBALE AND SILTATION FENCING BARRIERS AND OTHER EROSION AND SEDIMENT CONTROL MEASURES/DEVICES SHALL BE INSPECTED, CLEANED, REPLACED AND/OR REPAIRED AS NECESSARY, AND NO LESS THAN WEEKLY, AND AFTER EACH SIGNIFICANT RAINFALL. ACCUMULATED SEDIMENTS SHALL BE REMOVED WHEN THEY REACH HALF THE HEIGHT OF THE BARRIER.

2.4. GENERAL

- 2.4.1. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH (USDA) NATURAL RESOURCES CONSERVATION SERVICE (NRCS, FORMERLY SCS) GUIDELINES AND ALL LOCAL MUNICIPAL REGULATIONS.
- 2.4.2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ESTABLISHING AND MAINTAINING ALL CONTROL POINTS AND BENCH MARKS NECESSARY FOR THE WORK.
- 2.4.3. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO THE COMMENCEMENT OF ANY SITEWORK OR EARTHWORK OPERATIONS, SHALL BE MAINTAINED DURING CONSTRUCTION, AND SHALL REMAIN IN PLACE UNTIL ALL SITEWORK IS COMPLETE AND GROUNDCOVER IS ESTABLISHED.
- 2.4.4. ALL WORK SHALL BE IN ACCORDANCE WITH THE PERMITS AND APPROVALS ISSUED BY THE LOCAL PLANNING BOARD, THEIR AGENTS, AND THE CONSTRUCTION SPECIFICATIONS.
- 2.4.5. STOCKPILES SHALL BE SURROUNDED ON THEIR PERIMETERS WITH STAKED BALES AND/OR SILTATION FENCES TO PREVENT AND/OR CONTROL SILTATION AND EROSION.
- 2.4.6. TOPS OF STOCKPILES SHALL BE COVERED IN SUCH A MANNER THAT STORMWATER DOES NOT INFILTRATE THE MATERIALS AND THEREBY RENDER THE SAME UNSUITABLE FOR FILL USE.

IF APPLICABLE, EFFORTS SHALL BE MADE TO AVOID STOCKPILING CUT GLACIAL TILL SOILS SINCE STOCKPILING INCREASES EXPOSURE TO PRECIPITATION AND PROVIDES GREATER OPPORTUNITY FOR FROST PENETRATION. SOME OF THE STEPS IN SEQUENCING MAY OCCUR SIMULTANEOUSLY, PARTICULARLY CUT AND FILL OPERATIONS, IN AN EFFORT TO AVOID STOCKPILING.

- 2.4.7. ALL DISTURBED OR EXPOSED AREAS SUBJECT TO EROSION SHALL BE STABILIZED WITH MULCH OR SEEDED FOR TEMPORARY VEGETATIVE COVER. NO AREA, SUBJECT TO EROSION SHALL BE LEFT DISTURBED AND UNSTABILIZED FOR PERIODS LONGER THAN IS ABSOLUTELY NECESSARY TO CARRY OUT THAT PORTION OF THE CONSTRUCTION WORK.
- 2.4.8. THE LOCATION OF TEMPORARY DRAINAGE SWALES AND SEDIMENTATION TRAPS ARE APPROXIMATE ONLY AND SHALL BE RELOCATED AS REQUIRED AS CONSTRUCTION PROGRESSES.
- 2.4.9. BALE DIKES SHALL BE CONSTRUCTED AT ALL EXISTING & PROPOSED CATCH BASINS LOCATED IN AREAS SUBJECT TO STORMWATER RUN-OFF FROM PROPOSED CONSTRUCTION, OR AS DIRECTED BY THE OWNER'S REPRESENTATIVE. NO SEDIMENTS SHALL ENTER THE OFF-SITE DRAINAGE SYSTEMS AT ANY TIME. SEDIMENT DISCHARGE TO OFF-SITE PROPERTY IS PROHIBITED.
- 2.4.10. CULVERT/PIPE INLETS AND OUTFALLS SHALL BE PROTECTED FROM INCOMING SILT UNTIL ALL DISTURBED AREAS TRIBUTARY TO THEM ARE PERMANENTLY STABILIZED.
- 2.4.11. ANY DEWATERING REQUIRED DURING CONSTRUCTING ON THE SITE SHALL DISCHARGE INTO A DEWATERING FILTER OR THE TEMPORARY SILT BASIN PRIOR TO DISCHARGE TO THE EXISTING DETENTION BASIN OR TO OFF-SITE .
- 2.4.12. BALES AND SILTATION FENCING AND TEMPORARY SILT BASIN SHALL BE INSPECTED NO LESS THAN WEEKLY AND AFTER EACH SIGNIFICANT RAINFALL AND REPLACED AS REQUIRED.
- 2.4.13. ALL PROPOSED NON-RIPRAP SLOPES STEEPER THAN 3:1 SHALL BE STABILIZED WITH EROSION CONTROL FABRIC AND PROTECTED FROM EROSION.
- 2.4.14. THE CONTRACTOR SHALL KEEP ON SITE AT ALL TIMES ADDITIONAL BALES AND EXTRA SILTATION FENCING FOR INSTALLATION AT THE DIRECTION OF THE OWNER'S REPRESENTATIVE OR THE MUNICIPAL AGENTS TO MITIGATE ANY EMERGENCY CONDITION.
- 2.4.15. BORINGS WERE TAKEN FOR THE PURPOSE OF DESIGN AND SHOW CONDITIONS AT BORING POINTS ONLY. THEY DO NOT NECESSARILY SHOW THE NATURE OF ALL MATERIALS TO BE ENCOUNTERED DURING CONSTRUCTION.
- 2.4.16. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND PAYING FOR ANY PERMITS AND/OR CONNECTION FEES REQUIRED TO CARRY OUT THE WORK INCLUDING BUT NOT LIMITED TO DEMOLÍTION.
- 2.4.17. DISPOSAL OF ALL DEMOLISHED MATERIALS IS THE RESPONSIBILITY OF THE CONTRACTOR AND MUST BE OFF-SITE IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL MUNICIPAL REQUIREMENTS.
- 2.4.18. THE CONTRACTOR SHALL PROTECT AND/OR CAP OFF ALL EXISTING ON- SITE UTILITY SERVICES DESIGNATED ON THESE DRAWINGS. SERVICES SHALL BE CAPPED OFF WHERE SAME ENTER THE PERIMETER PROPERTY LINE.
- 2.4.19. THE LIMIT OF WORK LINE FOR THE AREA TO BE CLEARED AND GRUBBED SHALL BE THE SAME AS THE LIMIT OF WORK LINE NECESSARY FOR GRADING PURPOSES, (I.E., THE GRADING LIMITS AROUND THE PERIMETER OF THE PROJECT AREA).
- 2.4.20. THE AREA OR AREAS OF ENTRANCE AND EXIT TO AND FROM THE SITE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED IMMEDIATELY.
- 2.4.21. FOLLOWING THE ADDITION OF A BINDER COURSE, THE CONTRACTOR SHALL SWEEP ALL ON-SITE PAVEMENT, IF NECESSARY, UNTIL ALL SITE CONSTRUCTION IS COMPLETED.

TOWN OF TOPSFIELD, MA SITE PLAN REVIEW AND SPECIAL PERMIT

	·

WILLIAMS CIVIL No.43119 PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC. DATE DESCRIPTION REV APPLICANT\OWNER: SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE ANDOVER, MA 01810 PROJECT: RESIDENTIAL DEVELOPMENT 470 BOSTON STREET (ROUTE 1)

NONE DWG. NAME: C-2165-01A DMR | CHECKED BY: DESIGNED BY: ON PERMITTING

PROJECT NO.

TOPSFIELD, MA

2165-01A DATE:

10-13-2016

SHEET No.

ABB-3

ASSOCIATES. INC ivil & structural engineering + land surveying nvironmental consulting + landscape architecture

> 10 MAIN STREET LAKEVILLE, MA 02347-1674 TEL: (508) 923-1010

FAX: (508) 923-6309 WOBURN, MA . LAKEVILLE, MA . MANCHESTER, N

www.allenmajor.com

THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT. CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD

COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.

DRAWING TITLE:


0


OT

ABBREVIATIONS & NOTES

Copyright ©2016 Allen & Major Associates, Inc.

N:\PROJECTS\2165-01A\CIVIL\DRAWINGS\CURRENT\C-2165-01A - ABBREVIATIONS & NOTES.DWG





PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC. SARKIS DEVELOPMENT COMPANY

RESIDENTIAL DEVELOPMENT 470 BOSTON STREET (ROUTE 1) TOPSFIELD, MA

10-13-2016 1"=50' DWG. NAME: C-2165-01A DMR | CHECKED BY:

ASSOCIATES, INC.


LAKEVILLE, MA 02347-1674


TEL: (508) 923-1010 FAX: (508) 923-6309


WOBURN, MA . LAKEVILLE, MA . MANCHESTER, NI


THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT. CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.


SHEET No. LAYOUT & MATERIALS PLAN





















































TOWN OF TOPSFIELD, MA SITE PLAN REVIEW AND SPECIAL PERMIT

3	(

WILLIAMS CIVIL

PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC.


	I		
REV	DATE	DESCRIPTION	

SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE ANDOVER, MA 01810

PROJECT:

RESIDENTIAL DEVELOPMENT **470 BOSTON STREET (ROUTE 1)** TOPSFIELD, MA

2165-01A DATE: PROJECT NO. 10-13-2016 N.T.S. DWG. NAME: C-2165-01A DMR | CHECKED BY: DESIGNED BY:



ASSOCIATES, INC. civil & structural engineering + land surveying

environmental consulting + landscape architecture www.allenmajor.com 10 MAIN STREET

LAKEVILLE, MA 02347-1674 TEL: (508) 923-1010 FAX: (508) 923-6309

WOBURN, MA . LAKEVILLE, MA . MANCHESTER, NE


THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT. CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.


SHEET No.


DRAWING TITLE:


DETAILS


Copyright©2016 Allen & Major Associates, Inc. All Rights Reserved

















ALL TRAFFIC AND SAFETY SIGNAGE SHALL COMPLY WITH LATEST MUTCD STANDARDS.

*COORDINATE DIRECTION OF ARROWS WITH TRAFFIC DIRECTIONAL

SIGN TABLE NOT TO SCALE







TOWN OF TOPSFIELD, MA	
SITE PLAN REVIEW	
AND SPECIAL PERMIT	


SITE PLAN AN	D SPECIAL PERMIT	APPROVAL
\$ 		
SIGNA TURE		DATE

Τ	APPROVAL		9
			Z
	and the second s		
			<u> </u>
-10%	0	DATE	2
			ļ

DRAWING TITLE:

Copyright ©2016 Allen & Major Associates, Inc.

N:\PROJECTS\2165-01A\CIVIL\DRAWINGS\CURRENT\C-2165-01A - DETAILS.DWG



PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC.

REV DATE DESCRIPTION

APPLICANT\OWNER: SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE

ANDOVER, MA 01810

RESIDENTIAL DEVELOPMENT **470 BOSTON STREET (ROUTE 1)** TOPSFIELD, MA

	PROJECT NO.	2165-01A	DATE:	10-13-20
	SCALE:	N.T.S.	DWG. NAME:	C-2165-0
	DESIGNED BY:	DMR	CHECKED BY:	
J	PREPARED BY:			



ASSOCIATES, INC.

environmental consulting + landscape architecture

www.allenmajor.com 10 MAIN STREET


LAKEVILLE, MA 02347-1674 TEL: (508) 923-1010 FAX: (508) 923-6309


WOBURN, MA ♦ LAKEVILLE, MA ♦ MANCHESTER, NH THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT.


SHEET No.


CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA, PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.


DETAILS























1. SURFACE COURSE, BASE, AND SUBGRADE SHALL BE PER GEO-TECHNICAL ENGINEER'S RECOMMENDATIONS FOR LOCAL SOILS OR DRAINAGE CONDITIONS AND/OR METHODS.

- 2. SUBGRADE SHALL BE COMPACTED TO 95% OF PROCTOR.
- 3. COORDINATE PAVEMENT DETAIL WITH GEO-TECH & ENGINEER.
- 4. FOR ANY PAVING IN ROUTE 1, CONTRACTOR TO MA DOT STANDARDS AT NO ADDITIONAL COST TO THE OWNERS. COORD. WITH MA DOT & NEERING DEPT.

STANDARD DUTY PAVING


- A = 1.5" ASPHALT CONCRETE SURFACE COURSE (M3.11.03, TABLE A, TOP COURSE)
 1.5" ASPHALT CONCRETE BINDER COURSE (M3.11.03, TABLE A, BINDER COURSE)
- B = 12" BASE COURSE SAND AND GRAVEL FILL

HEAVY DUTY PAVING

- A = 1.5" ASPHALT CONCRETE SURFACE COURSE (M3.11.03, TABLE A, TOP COURSE)
 2.5" ASPHALT CONCRETE BINDER COURSE (M3.11.03, TABLE A, BINDER COURSE)
- B = 12" BASE COURSE SAND AND GRAVEL FILL

STANDARD & HEAVY DUTY BITUMINOUS ROADWAY

NOT TO SCALE



PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC.

REV DATE DESCRIPTION

APPLICANT\OWNER:

SARKIS DEVELOPMENT COMPANY
2 ELM SQUARE
ANDOVER, MA 01810

PREPARED BY:		
		1
ALLEN	& MA	JOR

RESIDENTIAL DEVELOPMENT

470 BOSTON STREET (ROUTE 1)

TOPSFIELD, MA

2165-01A DATE:

N.T.S. DWG. NAME: C-2165-01/

DMR | CHECKED BY:

PROJECT NO.

DESIGNED BY:

SCALE:

10-13-201

SHEET No.

ALLEN & MAJOR
ASSOCIATES, INC.
civil & structural engineering • land surveyin

nvironmental consulting • landscape architecture
www.allenmajor.com

10 MAIN STREET
LAKEVILLE, MA 02347-1674
TEL: (508) 923-1010
FAX: (508) 923-6309


FAX: (508) 923-6309
WOBURN, MA ◆ LAKEVILLE, MA ◆ MANCHESTER, NE


THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT.
CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED
COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR
HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS
PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION
MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR
ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S
AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF
THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD
COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.


DETAILS

DRAWING TITLE:

Copyright@2016 Allen & Major Associates, Inc.
All Rights Reserved









TRENCH DETAIL


NOT TO SCALE


CONDITION & PIPE	**SELECT MATERIAL	LINING MATERIAL	Y-DIMENSION
DUCTILE IRON "ORDINARY SOIL"	TYPE I, II, OR III	SAND OR TYPE III	3"
RCP "ORDINARY SOIL"	TYPE II OR III	SAND OR TYPE III	3"
ALL PIPE OVER BEDROCK OR LEDGE	TYPE II OR III	SAND OR TYPE III	8"
DUCTILE IRON IN CLAY OR MUCK	TYPE II OR III	SAND	4"
RCP IN CLAY	TYPE II OR III	SAND	8"
ALL PLASTICS	TYPE III	SAND OR TYPE III	6"

- * SUITABLE MATERIAL SHALL CONTAIN NO STONE GREATER THAN 4" IN DIAMETER, NO FROZEN LUMPS, AND ONLY MINOR AMOUNTS OF CLAY OR ORGANIC MATERIAL, ALL MATERIAL TO BE PLACED IN MAX 12" LIFTS AND COMPACTED BEFORE PLACING NEXT LIFT.
- **TYPE I MATERIAL SHALL BE EITHER GRAVEL OR EXCAVATED MATERIAL CONTAINING NO STONES GREATER THAN 1.5" DIAMETER, NO FROZEN LUMPS, CLAY OR ORGANIC MATERIAL
- **TYPE II MATERIAL SHALL BE CLEAN, HARD, CRUSHED OR NATURAL STONE WITH A GRADATION BY WEIGHT OF 100% PASSING A 1.5" SQUARE OPENING, NOT MORE THAN 25% PASSING A 3" OPENING, AND NOT MORE THAN 5% PASSING A 3" SQUARE OPENING.
- **TYPE III MATERIAL SHALL BE CLEAN, HARD, CRUSHED STONE FREE FROM COATINGS AND THOROUGHLY WASHED WITH A GRADATION BY WEIGHT OF 100% PASSING A 1" SQUARE OPENING, AND 0 TO 5% PASSING A 1" SQUARE OPENING.










1. NUMBER OF LACING RODS IS BASED ON MAXIMUM PRESSURE OF 125 P.S.I.

- 2. EYE-BOLTS AND LACING RODS ARE TO BE FABRICATED FROM A-36 STEEL.
- 3. STEEL LACING RODS SHALL HAVE A YIELD STRESS OF NOT LESS THAN 36,000 P.S.I.
- 4. EYE-BOLTS SHALL HAVE A MINIMUM TENSILE STRENGTH OF 7,000 LBS. EACH.


MECHANICAL JOINT LACING DETAIL NOT TO SCALE




SEWER MAIN AND A WATER MAIN:

- 1. THE WATER MAIN SHALL BE LAID IN A SEPARATE TRENCH AND THE DIFFERENCE IN ELEVATION BETWEEN THE WATER MAIN AND THE SEWER MAIN SHALL BE AT LEAST 18 INCHES
- THE PIPE CROSSING SHALL OCCUR AS CLOSE TO 90° AS PRACTICABLE. 3. THE PIPE JOINTS SHALL BE STAGGERED TO PROVIDE THE MAXIMUM SEPARATION FROM THE POINT OF CROSSING.
- 4. THE CROSSING SHALL BE ENCASED IN CONCRETE FOR THE ENTIRE WIDTH OF THE TRENCH AND FOR A DISTANCE OF 8 LINEAR FEET CENTERED ON THE CROSSING.

SEWER / WATER CROSSING DETAIL	(7)
NOT TO SCALE	



TOWN OF TOPSFIELD, MA SITE PLAN REVIEW AND SPECIAL PERMIT			
SITE PLAN AND SPECIAL PERMIT APPROVAL			
SIGNA TURE	DATE		



PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC.

REV	DATE	DESCRIPTION	

APPLICANT\OWNER: SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE ANDOVER, MA 01810

PROJECT:

RESIDENTIAL DEVELOPMENT 470 BOSTON STREET (ROUTE 1) TOPSFIELD, MA

	PROJECT NO.	2165-01A	DATE:	10-13-201
	SCALE:	N.T.S.	DWG. NAME:	C-2165-01
_	DESIGNED BY:	DMR	CHECKED BY:	ı



ASSOCIATES, INC. civil & structural engineering + land surveying

environmental consulting + landscape architecture www.allenmajor.com

10 MAIN STREET LAKEVILLE, MA 02347-1674 TEL: (508) 923-1010 FAX: (508) 923-6309

WOBURN, MA . LAKEVILLE, MA . MANCHESTER, NI

THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT. CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.

SHEET No.


D-4


DRAWING TITLE:


0


DETAILS


Copyright@2016 Allen & Major Associates, Inc. All Rights Reserved












THE USE OF FLEXIBLE CONNECTIONS IS RECOMMENDED AT THE INLET AND OUTLET WHERE APPLICABLE.

2. THE COVER SHOULD BE POSITIONED OVER THE 24" OUTLET RISER PIPE AND THE 6" OIL PORT. 3. THE STORMCEPTOR SYSTEM IS PROTECTED BY ONE OR MORE OF THE FOLLOWING

U.S. PATENTS: #4985148, #5498331, #5725760, #5753115, #5849181. 4. CONTACT A CONCRETE PIPE DIVISION REPRESENTATIVE FOR FÜRTHER DETAILS NOT LISTED ON THIS DRAWING.

> STC 450i PRECAST CONCRETE STORMCEPTOR 4 (450 US GALLON CAPACITY)

> > NOT TO SCALE



1. THE USE OF FLEXIBLE CONNECTIONS IS RECOMMENDED AT THE INLET AND OUTLET WHERE APPLICABLE.

2. THE COVER SHOULD BE POSITIONED OVER THE 24" OUTLET RISER PIPE AND THE 6"Ø OIL PORT. THE STORMCEPTOR SYSTEM IS PROTECTED BY ONE OR MORE OF THE FOLLOWING

U.S. PATENTS: #4985148, #5498331, #5725760, #5753115, #5849181.

CONTACT A CONCRETE PIPE DIVISION REPRESENTATIVE FOR FÜRTHER DETAILS NOT LISTED ON THIS DRAWING.

> STC 900 PRECAST CONCRETE STORMCEPTOR 5 (900 US GALLON CAPACITY)

NOT TO SCALE

TOWN OF TOP SITE PLAN **AND SPECIA**

Afficiacy interesting the selection of the		
	Commo) con casa grant a sample	

	١
SFIELD, MA	1
REVIEW	1
L PERMIT	1
	-

	191
 SIGNATURE	DATE

WILLIAMS

PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC.

DATE DESCRIPTION

APPLICANT\OWNER: SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE

ANDOVER, MA 01810

PROJECT:

RESIDENTIAL DEVELOPMENT 470 BOSTON STREET (ROUTE 1) TOPSFIELD, MA

	PROJECT NO.	2165-01A	DATE:	10-13-20
	SCALE:	AS NOTED	DWG. NAME:	C-2165-0
>	DESIGNED BY:	DMR	CHECKED BY:	



ASSOCIATES, INC. ivil & structural engineering + land surveying nvironmental consulting • landscape architecture

www.allenmajor.com 10 MAIN STREET LAKEVILLE, MA 02347-1674 TEL: (508) 923-1010

FAX: (508) 923-6309 WOBURN, MA ♦ LAKEVILLE, MA ♦ MANCHESTER, NH

THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT. CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD

SHEET No.


D-5


COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.

DRAWING TITLE:

DETAILS

Copyright ©2016 Allen & Major Associates, Inc. All Rights Reserved






& APPROVE FINAL WALL DESIGN FOR STRUCTURAL INTEGRITY AT CONTRACTOR COST. CONTRACTOR TO INCORPORATE ANY NECESSARY REVISIONS AT NO ADDITIONAL COST.

2. PROVIDE SHOP DRAWING FOR MANUFACTURERS WALL DESIGN, GEOREINFORCEMENT BLOCK STYLE & COLOR, DRAIN PIPE, LEVELING PAD, (DETAILS & SECTIONS & ELEVATIONS) FOR APPROVAL PRIOR TO PURCHASE.

3. INSTALL PER MANUFACTURERS, GEOTECHNICAL ENGINEERS & STRUCTURAL ENGINEERS RECOMMENDATIONS AT CONTRACTOR COST.

> TYPICAL PRECAST CONC. SEGMENTAL **RETAINING WALL** NOT TO SCALE



1. STRUCTURAL ENGINEER LICENSED IN THE STATE OF MASSACHUSETTS TO REVIEW & APPROVE FINAL WALL DESIGN FOR STRUCTURAL INTEGRITY AT CONTRACTOR COST. CONTRACTOR TO INCORPORATE ANY NECESSARY REVISIONS AT NO ADDITIONAL COST.

2. PROVIDE SHOP DRAWING FOR MANUFACTURERS WALL DESIGN (DETAILS & SECTIONS & ELEVATIONS) FOR APPROVAL PRIOR TO PURCHASE.

3. INSTALL PER MANUFACTURERS, GEOTECHNICAL ENGINEERS & STRUCTURAL ENGINEERS RECOMMENDATIONS AT CONTRACTOR COST.

BASE LEVELING PAD NOTES:


1. THE LEVELING PAD IS TO BE CONSTRUCTED OF CRUSHED STONE OR 4000 PSI UNREINFORCED CONCRETE

2. THE BASE FOUNDATION IS TO BE APPROVED BY THE SITE GEOTECHNICAL ENGINEER AT CONTRACTOR COST PRIOR TO PLACEMENT OF THE LEVELING PAD.

> STANDARD PRECAST CONC. UNIT/BASE PAD ISOMETRIC SECTION VIEW

NOT TO SCALE

SLEEVE-IT (OR APPROVED EQUAL) FOR MORE INFORMATION CONTACT: ADVANCED HARDSCAPE SOLUTIONS LLC FENCE POST (SEE-1-866-843-0500 OR INFO@ADVANCEDHARDSCAPE.COM NOTE #1) SLEEVE-IT 1224R 12"øX24" DEEP CAP UNIT-SET POSITION OF-SLEEVE IMMEDIATELY BEHIND SRW UNIT. FILL SLEEVE WITH CONCRETE, SET GUARDRAIL POST. CUT THE GEOGRID -AROUND THE SLEEVE-IT SYSTEM AS NECESSARY SRW UNIT ---COMPACT TO 95% REINFORCED (MAX DRY DENSITY) BACKFILL ZONE GEOGRID (TYPICAL) FENCING SYSTEMS APPROVED FOR USE WITH SLEEVE-IT 1224R ARE LIMITED TO THE FOLLOWING HEIGHTS: A. CHAIN LINK - UP TO 8-FT, B. PRIVACY - UP TO 6-FT (WOODEN, PVC, METAL). FENCE POST AT TOP OF MODULAR BLOCK RETAINING WALL NOT TO SCALE



TOWN OF TOPSFIELD, MA SITE PLAN REVIEW AND SPECIAL PERMIT

SITE PLAN AND SPECIAL PERMIT APPRO	VAL
And the second s	
SIGNATURE	DATE

PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC.

DATE DESCRIPTION REV APPLICANT\OWNER:

SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE ANDOVER, MA 01810

PROJECT:

RESIDENTIAL DEVELOPMENT **470 BOSTON STREET (ROUTE 1)** TOPSFIELD, MA

PROJECT NO.	2165-01A	DATE:	10-13-2016
SCALE:	N.T.S.	DWG. NAME:	C-2165-01A
DESIGNED BY:	DMR	CHECKED BY:	RB

PERMITTING ASSOCIATES, INC.

ivil & structural engineering . land surveying nvironmental consulting + landscape architectur www.allenmajor.com

> 10 MAIN STREET LAKEVILLE, MA 02347-1674 TEL: (508) 923-1010 FAX: (508) 923-6309

WOBURN, MA . LAKEVILLE, MA . MANCHESTER, NH


THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT. CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.


SHEET No.


D-6


DRAWING TITLE: **DETAILS**

Copyright ©2016 Allen & Major Associates, Inc. All Rights Reserved









PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC.

REV	DATE	DESCRIPTION	


APPLICANT\OWNER:

SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE ANDOVER, MA 01810

PROJECT:

RESIDENTIAL DEVELOPMENT 470 BOSTON STREET (ROUTE 1) TOPSFIELD, MA

2165-01A DATE: 10-13-2016 PROJECT NO. N.T.S. DWG. NAME: C-2165-01A SCALE: DESIGNED BY: DMR | CHECKED BY:



ASSOCIATES, INC.

ivil & structural engineering . land surveying nvironmental consulting + landscape architectur www.allenmajor.com

10 MAIN STREET LAKEVILLE, MA 02347-1674 TEL: (508) 923-1010 FAX: (508) 923-6309

WOBURN, MA ♦ LAKEVILLE, MA ♦ MANCHESTER, NI

THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT. CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.

DRAWING TITLE: **DETAILS**

SHEET No.

Copyright@2016 Allen & Major Associates, Inc. All Rights Reserved

TOWN OF TOPSFIELD, MA SITE PLAN REVIEW AND SPECIAL PERMIT

SITE PLAN AND SPECIAL PERMIT APPROVAL	
SIGNA TURE	DATE

CULTEC RECHARGER® 330XLHD PRODUCT SPECIFICATIONS

CULTEC RECHARGER 330XLHD CHAMBERS ARE DESIGNED FOR UNDERGROUND STORMWATER MANAGEMENT. THE CHAMBERS MAY BE USED FOR RETENTION, RECHARGING, DETENTION OR CONTROLLING THE FLOW OF ON-SITE STORMWATER RUNOFF.

THE CHAMBERS WILL BE MANUFACTURED BY CULTEC, INC. OF BROOKFIELD, CT (203-775-4416 OR 1-800-428-5832).

- 2. THE CHAMBER WILL BE VACUUM THERMOFORMED OF BLACK POLYETHYLENE.
- 3. THE CHAMBER WILL BE ARCHED IN SHAPE.
- 4. THE CHAMBER WILL BE OPEN-BOTTOMED.
- 5. THE CHAMBER WILL BE JOINED USING AN INTERLOCKING OVERLAPPING RIB METHOD, CONNECTIONS MUST BE FULLY SHOULDERED OVERLAPPING RIBS, HAVING NO SEPARATE COUPLINGS OR SEPARATE END WALLS
- 6. THE NOMINAL CHAMBER DIMENSIONS OF THE CULTEC RECHARGER 330XLHD SHALL BE 30.5 INCHES (775 mm) TALL, 52 INCHES (1321 mm) WIDE AND 8.5 FEET (2.59 m) LONG. THE INSTALLED LENGTH OF A JOINED RECHARGER 330XLHD SHALL
- 7. MAXIMUM INLET OPENING ON THE CHAMBER END WALL IS 24 INCHES (600 mm).
- 8. THE CHAMBER WILL HAVE TWO SIDE PORTALS TO ACCEPT CULTEC HVLV® FC-24 FEED CONNECTORS TO CREATE AN INTERNAL MANIFOLD. THE NOMINAL DIMENSIONS OF EACH SIDE PORTAL WILL BE 10.5 INCHES (267 mm) HIGH BY 11.5 INCHES (292 mm) WIDE. MAXIMUM ALLOWABLE OUTER DIAMETER (O.D.) PIPE SIZE IN THE SIDE PORTAL IS 11.75 INCHES
- 9. THE NOMINAL CHAMBER DIMENSIONS OF THE CULTEC HVLV FC-24 FEED CONNECTOR SHALL BE 12 INCHES (305 mm) TALL, 16 INCHES (406 mm) WIDE AND 24.2 INCHES (614 mm) LONG.
- 10. THE NOMINAL STORAGE VOLUME OF THE RECHARGER 330XLHD CHAMBER WILL BE 7.459 FT3 / FT (0.693 m3 / m) WITHOUT STONE. THE NOMINAL STORAGE VOLUME OF A JOINED RECHARGER 330XLHD SHALL BE 52.213 FT3 / UNIT (1.478 m3 / UNIT) -
- 11. THE NOMINAL STORAGE VOLUME OF THE HVLV FC-24 FEED CONNECTOR WILL BE 0.913 FT³ / FT (0.085 m³ / m) WITHOUT
- 12. THE RECHARGER 330XLHD CHAMBER WILL HAVE FIFTY-SIX DISCHARGE HOLES BORED INTO THE SIDEWALLS OF THE UNIT'S CORE TO PROMOTE LATERAL CONVEYANCE OF WATER.
- 13. THE RECHARGER 330XLHD CHAMBER SHALL HAVE 16 CORRUGATIONS.
- 14. THE END WALL OF THE CHAMBER, WHEN PRESENT, WILL BE AN INTEGRAL PART OF THE CONTINUOUSLY FORMED UNIT. SEPARATE END PLATES CANNOT BE USED WITH THIS UNIT.
- 15. THE RECHARGER 330XLRHD STAND ALONE UNIT MUST BE FORMED AS A WHOLE CHAMBER HAVING TWO FULLY FORMED INTEGRAL END WALLS AND HAVING NO SEPARATE END PLATES OR SEPARATE END WALLS.
- 16. THE RECHARGER 330XLSHD STARTER UNIT MUST BE FORMED AS A WHOLE CHAMBER HAVING ONE FULLY FORMED INTEGRAL END WALL AND ONE PARTIALLY FORMED INTEGRAL END WALL WITH A LOWER TRANSFER OPENING OF 14 INCHES (356 mm) HIGH X 34.5 INCHES (876 mm) WIDE.
- 17. THE RECHARGER 330XLIHD INTERMEDIATE UNIT MUST BE FORMED AS A WHOLE CHAMBER HAVING ONE FULLY OPEN ENDWALL AND ONE PARTIALLY FORMED INTEGRAL END WALL WITH A LOWER TRANSFER OPENING OF 14 INCHES (356 mm)
- HIGH X 34.5 INCHES (876 mm) WIDE. 18. THE RECHARGER 330XLEHD END UNIT MUST BE FORMED AS A WHOLE CHAMBER HAVING ONE FULLY FORMED INTEGRAL END WALL AND ONE FULLY OPEN END WALL AND HAVING NO SEPARATE END PLATES OR END WALLS
- 19. THE HVLV FC-24 FEED CONNECTOR MUST BE FORMED AS A WHOLE CHAMBER HAVING TWO OPEN END WALLS AND HAVING NO SEPARATE END PLATES OR SEPARATE END WALLS. THE UNIT WILL FIT INTO THE SIDE PORTALS OF THE RECHARGER 330XLHD AND ACT AS CROSS FEED CONNECTIONS.
- 20. CHAMBERS MUST HAVE HORIZONTAL STIFFENING FLEX REDUCTION STEPS BETWEEN THE RIBS.
- 21.HEAVY DUTY UNITS ARE DESIGNATED BY A COLORED STRIPE FORMED INTO THE PART ALONG THE LENGTH OF THE
- 22.THE CHAMBER WILL HAVE A 6 INCH (152 mm) DIAMETER RAISED INTEGRAL CAP LOCATED ON TOP OF THE ARCH IN THE CENTER OF EACH UNIT TO BE USED AS AN OPTIONAL INSPECTION PORT OR CLEAN-OUT
- 23.THE UNITS MAY BE TRIMMED TO CUSTOM LENGTHS BY CUTTING BACK TO ANY CORRUGATION.
- 24.THE CHAMBER SHALL BE MANUFACTURED IN AN ISO 9001:2008 CERTIFIED FACILITY.
- 25.MAXIMUM ALLOWED COVER OVER TOP OF UNIT SHALL BE 12 FEET (3.66 m)
- 26.THE CHAMBER WILL BE DESIGNED TO WITHSTAND TRAFFIC LOADS WHEN INSTALLED ACCORDING TO CULTEC'S RECOMMENDED INSTALLATION INSTRUCTIONS

CULTEC HVLV FC-24 FEED CONNECTOR PRODUCT SPECIFICATIONS

CULTEC HVLV FC-24 FEED CONNECTORS ARE DESIGNED TO CREATE AN INTERNAL MANIFOLD FOR CULTEC RECHARGER MODEL 330XLHD STORMWATER CHAMBERS.

CHAMBER PARAMETERS


- 1. THE CHAMBERS WILL BE MANUFACTURED BY CULTEC, INC. OF BROOKFIELD, CT. (203-775-4416 OR 1-800-428-5832)
- 2. THE CHAMBER WILL BE VACUUM THERMOFORMED OF BLACK HIGH MOLECULAR WEIGHT HIGH DENSITY POLYETHYLENE
- 3. THE CHAMBER WILL BE ARCHED IN SHAPE.
- 4. THE CHAMBER WILL BE OPEN-BOTTOMED.
- 5. THE NOMINAL CHAMBER DIMENSIONS OF THE CULTEC HVLV FC-24 FEED CONNECTOR SHALL BE 12 INCHES (305 mm) TALL, 16 INCHES (406 mm) WIDE AND 24.2 INCHES (614 mm) LONG.
- 6. THE NOMINAL STORAGE VOLUME OF THE HVLV FC-24 FEED CONNECTOR WILL BE 0.913 FT³ / FT (0.085 m³ / m) WITHOUT STONE.
- 7. THE HVLV FC-24 FEED CONNECTOR CHAMBER SHALL HAVE 2 CORRUGATIONS.
- 8. THE HVLV FC-24 FEED CONNECTOR MUST BE FORMED AS A WHOLE CHAMBER HAVING TWO OPEN END WALLS AND HAVING NO SEPARATE END PLATES OR SEPARATE END WALLS. THE UNIT WILL FIT INTO THE SIDE PORTALS OF THE CULTEC RECHARGER STORMWATER CHAMBER AND ACT AS CROSS FEED CONNECTIONS CREATING AN INTERNAL MANIFOLD.
- 9. THE CHAMBER WILL BE DESIGNED TO WITHSTAND TRAFFIC LOADS WHEN INSTALLED ACCORDING TO CULTEC'S RECOMMENDED.
- 10. THE CHAMBER SHALL BE MANUFACTURED IN AN ISO 9001:2008 CERTIFIED FACILITY


CULTEC NO. 66™ WOVEN GEOTEXTILE


CULTEC NO. 66™ WOVEN GEOTEXTILE IS UTILIZED AS AN UNDERLAYMENT TO PREVENT SCOURING CAUSED BY WATER MOVEMENT WITHIN THE CULTEC CHAMBERS AND FEED CONNECTORS UTILIZING THE CULTEC MANIFOLD FEATURE.

GEOTEXTILE PARAMETERS

- 1. THE GEOTEXTILE SHALL BE PROVIDED BY CULTEC, INC. OF BROOKFIELD, CT. (203-775-4416 OR 1-800-428-5832)
- 2. THE GEOTEXTILE SHALL BE BLACK IN APPEARANCE.
- 3. THE GEOTEXTILE SHALL HAVE A TENSILE STRENGTH OF 315 LBS (1.40KN) PER ASTM D4632 TESTING METHOD.
- 4. THE GEOTEXTILE SHALL HAVE A TENSILE ELONGATION RESISTANCE OF 15% PER ASTM D4632 TESTING METHOD.
- 5. THE GEOTEXTILE SHALL HAVE A MULLEN BURST RESISTANCE OF 600PSI (4138 KPA) PER ASTM D3786 TESTING METHOD. 6. THE GEOTEXTILE SHALL HAVE A TEAR RESISTANCE OF 115 LBS (0.51 KN) PER ASTM D4533 TESTING METHOD.
- 7. THE GEOTEXTILE SHALL HAVE A PUNCTURE RESISTANCE OF 150 LBS (0.66 KN) PER ASTM D4833 TESTING METHOD.
- 8. THE GEOTEXTILE SHALL HAVE A CBR PUNCTURE RESISTANCE OF 900 LBS (4.00 KN) PER ASTM D6241 TESTING METHOD. 9. THE GEOTEXTILE SHALL HAVE A UV RESISTANCE OF 70% @ 500 HRS. PER ASTM D4355 TESTING METHOD.
- 10. THE GEOTEXTILE SHALL HAVE A PERMITTIVITY RATING OF 0.05 SEC-1 PER ASTM D4491 TESTING METHOD.
- 11. THE GEOTEXTILE SHALL HAVE A WATER FLOW RATING OF 4 GPM/FT2 (160 LPM/M2) PER ASTM D4491 TESTING METHOD.
- 12. THE GEOTEXTILE SHALL HAVE A PERCENT OPEN AREA OF <1% PER CW-02215 TESTING METHOD.
- 13. THE GEOTEXTILE SHALL HAVE AN APPARENT OPENING SIZE OF 40 US STD. SIEVE (0.425 MM) PER ASTM D4751 TESTING METHOD. 14. THE GEOTEXTILE SHALL CONSIST OF A 100% HIGH-TENACITY, SILT-FILM POLYPROPYLENE YARNS.







CROSS SECTION

1) SEE A&M GRADING & DRAINAGE PLANS FOR ALL INVERTS & ELEVATIONS.



NEENAH FOUNDRY MODEL R-5900-A

PVC CLEAN-OUT CAP

(OR EQUAL) HEAVY DUTY FRAME AND LID

ADAPTER W/ SCREW-IN CAP

6.0" SDR-35 / SCH. 40 PVC RISER

~12.0" SDR-35 / SCH. 40 PVC COLLAR

FIELD PLACED CLASS "C" CONCRETE

MAINTAIN 6.0" CLEARANCE BETWEEN HEAVY DUTY LID AND

6.0" SDR-35 / SCH. 40 PVC ENDCAP CLEAN-OUT

SIGNA TURE	DATE

SITE PLAN AND SPECIAL PERMIT APPROVAL



PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC.

	T\OWNER:	DESCRIPTION	
REV	DATE	DESCRIPTION	
			-,000-41.55-50

SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE ANDOVER, MA 01810

RESIDENTIAL DEVELOPMENT 470 BOSTON STREET (ROUTE 1) TOPSFIELD, MA

 PROJECT NO.	2165-01A	DATE:	10-13-20
SCALE:	N.T.S.	DWG. NAME:	C-2165-0
DESIGNED BY:	DMR	CHECKED BY:	



nvironmental consulting • landscape architecture www.allenmajor.com

10 MAIN STREET LAKEVILLE, MA 02347-1674 TEL: (508) 923-1010

FAX: (508) 923-6309 WOBURN, MA ♦ LAKEVILLE, MA ♦ MANCHESTER, N

THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT. CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA, PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD

COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.

SHEET No.

D-8

DRAWING TITLE: DETAILS

Copyright@2016 Allen & Major Associates, Inc.

N:\PROJECTS\2165-01A\CIVIL\DRAWINGS\CURRENT\C-2165-01A - DETAILS.DWG

14.5"

-

10.25"

INSPECTION PORT DETAIL

PAVEMEN'

12" MIN.

6.0" SDR-35 / SCH 40 PVC

OR FINISHED GRADE

CULTEC RECHARGER® 280HD SPECIFICATIONS

CULTEC RECHARGER 280HD CHAMBERS ARE DESIGNED FOR UNDERGROUND STORMWATER MANAGEMENT. THE CHAMBERS MAY BE USED FOR RETENTION, RECHARGING, DETENTION OR CONTROLLING THE FLOW OF ON-SITE STORMWATER RUNOFF.

CHAMBER PARAMETERS

- 1. THE CHAMBERS WILL BE MANUFACTURED IN THE U.S.A. BY CULTEC, INC. OF BROOKFIELD, CT. (203-775-4416 OR 1-800-428-5832)
- 2. THE CHAMBER WILL BE VACUUM THERMOFORMED OF BLACK HIGH MOLECULAR WEIGHT HIGH DENSITY POLYETHYLENE (HMWHDPE).
- 3. THE CHAMBER WILL BE ARCHED IN SHAPE.
- THE CHAMBER WILL BE OPEN-BOTTOMED.
- 5. THE CHAMBER WILL BE JOINED USING AN INTERLOCKING OVERLAPPING RIB METHOD. CONNECTIONS MUST BE FULLY SHOULDERED OVERLAPPING RIBS, HAVING NO SEPARATE COUPLINGS OR SEPARATE
- 6. THE NOMINAL CHAMBER DIMENSIONS OF THE CULTEC RECHARGER 280HD SHALL BE 26.5 INCHES (673 mm) TALL, 47 INCHES (1194 mm) WIDE AND 8 FEET (2.44 m) LONG. THE INSTALLED LENGTH OF A JOINED RECHARGER 280HD SHALL BE 7 FEET (2.13 m).
- 7. MAXIMUM INLET OPENING ON THE CHAMBER ENDWALL IS 18 INCHES (450 mm).
- 8. THE CHAMBER WILL HAVE TWO SIDE PORTALS TO ACCEPT CULTEC HVLV® FC-24 FEED CONNECTORS TO CREATE AN INTERNAL MANIFOLD. NOMINAL INSIDE DIMENSIONS OF THE SIDE PORTAL SHALL HAVE A WIDTH OF 11.25" [286 mm] AND HEIGHT OF 11.5" [292 mm]. THE SIDE PORTAL CAN ACCEPT A MAXIMUM OUTER DIAMETER (O.D.) PIPE SIZE OF 12.25 INCHES [311 mm].
- 9. THE NOMINAL CHAMBER DIMENSIONS OF THE CULTEC HVLV® FC-24 FEED CONNECTOR SHALL BE 12 INCHES (305 mm) TALL, 16 INCHES (406 mm) WIDE AND 24.2 INCHES (614 mm) LONG.
- 10. THE NOMINAL STORAGE VOLUME OF THE RECHARGER 280HD CHAMBER WILL BE 6.079 FT3 / FT (0.565 m³/m) - WITHOUT STONE. THE NOMINAL STORAGE VOLUME OF A JOINED RECHARGER 280HD SHALL BE 42.553 FT³ / UNIT (1.205 m³ / UNIT) - WITHOUT STONE.
- 11. THE NOMINAL STORAGE VOLUME OF THE HVLV FC-24 FEED CONNECTOR WILL BE 0.913 FT³ / FT (0.085 m3 / m) - WITHOUT STONE.
- 12. THE RECHARGER 280HD CHAMBER WILL HAVE EIGHTY-TWO DISCHARGE HOLES BORED INTO THE SIDEWALLS OF THE UNIT'S CORE TO PROMOTE LATERAL CONVEYANCE OF WATER.
- 13. THE RECHARGER 280HD CHAMBER SHALL HAVE 15 CORRUGATIONS.
- 14. THE ENDWALL OF THE CHAMBER, WHEN PRESENT, WILL BE AN INTEGRAL PART OF THE CONTINUOUSLY FORMED UNIT. SEPARATE END PLATES CANNOT BE USED WITH THIS UNIT
- 15. THE RECHARGER 280RHD STAND ALONE UNIT MUST BE FORMED AS A WHOLE CHAMBER HAVING TWO FULLY FORMED INTEGRAL ENDWALLS AND HAVING NO SEPARATE END PLATES OR SEPARATE END
- 16. THE RECHARGER 280SHD STARTER UNIT MUST BE FORMED AS A WHOLE CHAMBER HAVING ONE FULLY FORMED INTEGRAL ENDWALL AND ONE PARTIALLY FORMED INTEGRAL ENDWALL WITH A LOWER TRANSFER OPENING OF 9 INCHES (229 mm) HIGH X 35 INCHES (889 mm) WIDE.
- 17. THE RECHARGER 280IHD INTERMEDIATE UNIT MUST BE FORMED AS A WHOLE CHAMBER HAVING ONE FULLY OPEN ENDWALL AND ONE PARTIALLY FORMED INTEGRAL ENDWALL WITH A LOWER TRANSFER OPENING OF 9 INCHES (229 mm) HIGH X 35 INCHES (889 mm) WIDE.
- 18. THE RECHARGER 280EHD END UNIT MUST BE FORMED AS A WHOLE CHAMBER HAVING ONE FULLY FORMED INTEGRAL ENDWALL AND ONE FULLY OPEN END WALL AND HAVING NO SEPARATE END PLATES OR END WALLS.
- 19. THE HVLV FC-24 FEED CONNECTOR MUST BE FORMED AS A WHOLE CHAMBER HAVING TWO OPEN END WALLS AND HAVING NO SEPARATE END PLATES OR SEPARATE END WALLS. THE UNIT WILL FIT INTO THE SIDE PORTALS OF THE RECHARGER 280HD AND ACT AS CROSS FEED CONNECTIONS.
- 20. CHAMBERS MUST HAVE HORIZONTAL STIFFENING FLEX REDUCTION STEPS BETWEEN THE RIBS. 21. HEAVY DUTY UNITS ARE DESIGNATED BY A COLORED STRIPE FORMED INTO THE PART ALONG THE
- LENGTH OF THE CHAMBER. 22. THE CHAMBER WILL HAVE A RAISED INTEGRAL CAP AT THE TOP OF THE ARCH IN THE CENTER OF
- EACH UNIT TO BE USED AS AN OPTIONAL INSPECTION PORT OR CLEAN-OUT. 23. THE UNITS MAY BE TRIMMED TO CUSTOM LENGTHS BY CUTTING BACK TO ANY CORRUGATION.
- 24. THE CHAMBER SHALL BE MANUFACTURED IN AN IN AN ISO 9001:2008 CERTIFIED FACILITY
- 25. THE CHAMBER WILL BE DESIGNED TO WITHSTAND TRAFFIC LOADS WHEN INSTALLED ACCORDING TO CULTEC'S INSTALLATION INSTRUCTIONS.
- 26. MAXIMUM ALLOWED COVER OVER TOP OF UNIT SHALL BE 12 FEET (3.65 m).

CULTEC HVLV® FC-24 FEED CONNECTOR PRODUCT SPECIFICATIONS

GENERAL

CULTEC HVLV FC-24 FEED CONNECTORS ARE DESIGNED TO CREATE AN INTERNAL MANIFOLD FOR CULTEC RECHARGER 280HD STORMWATER CHAMBERS.

CHAMBER PARAMETERS


- 1. THE CHAMBERS WILL BE MANUFACTURED BY CULTEC, INC. OF BROOKFIELD, CT. (203-775-4416 OR 1-800-428-5832)
- 2. THE CHAMBER WILL BE VACUUM THERMOFORMED OF BLACK HIGH MOLECULAR WEIGHT HIGH DENSITY POLYETHYLENE (HMWHDPE).
- 3. THE CHAMBER WILL BE ARCHED IN SHAPE.
- 4. THE CHAMBER WILL BE OPEN-BOTTOMED.
- 5. THE NOMINAL CHAMBER DIMENSIONS OF THE CULTEC HVLV FC-24 FEED CONNECTOR SHALL BE 12 INCHES (305 mm) TALL, 16 INCHES (406 mm) WIDE AND 24.2 INCHES (614 mm) LONG.
- 6. THE NOMINAL STORAGE VOLUME OF THE HVLV FC-24 FEED CONNECTOR WILL BE 0.913 FT3 / FT
- 7. THE HVLV FC-24 FEED CONNECTOR CHAMBER SHALL HAVE 2 CORRUGATIONS.
- 8. THE HVLV FC-24 FEED CONNECTOR MUST BE FORMED AS A WHOLE CHAMBER HAVING TWO OPEN END WALLS AND HAVING NO SEPARATE END PLATES OR SEPARATE END WALLS. THE UNIT WILL FIT INTO THE SIDE PORTALS OF THE CULTEC RECHARGER STORMWATER CHAMBER AND ACT AS CROSS FEED CONNECTIONS CREATING AN INTERNAL MANIFOLD.
- 9. THE CHAMBER WILL BE DESIGNED TO WITHSTAND TRAFFIC LOADS WHEN INSTALLED ACCORDING TO CULTEC'S RECOMMENDED INSTALLATION INSTRUCTIONS.
- 10. THE CHAMBER SHALL BE MANUFACTURED IN AN ISO 9001:2008 CERTIFIED FACILITY.


CULTEC NO. 66™ WOVEN GEOTEXTILE


CULTEC NO. 66™ WOVEN GEOTEXTILE IS UTILIZED AS AN UNDERLAYMENT TO PREVENT SCOURING CAUSED BY WATER MOVEMENT WITHIN THE CULTEC CHAMBERS AND FEED CONNECTORS UTILIZING THE CULTEC MANIFOLD FEATURE.


GEOTEXTILE PARAMETERS

- 1. THE GEOTEXTILE SHALL BE PROVIDED BY CULTEC, INC. OF BROOKFIELD, CT. (203-775-4416 OR 1-800-428-5832)
- 2. THE GEOTEXTILE SHALL BE BLACK IN APPEARANCE.
- 3. THE GEOTEXTILE SHALL HAVE A TENSILE STRENGTH OF 315 LBS (1.40KN) PER ASTM D4632 TESTING METHOD.
- 4. THE GEOTEXTILE SHALL HAVE A TENSILE ELONGATION RESISTANCE OF 15% PER ASTM D4632 TESTING
- 5. THE GEOTEXTILE SHALL HAVE A MULLEN BURST RESISTANCE OF 600PSI (4138 KPA) PER ASTM D3786 TESTING METHOD.
- 6. THE GEOTEXTILE SHALL HAVE A TEAR RESISTANCE OF 115 LBS (0.51 KN) PER ASTM D4533 TESTING METHOD.
- 7. THE GEOTEXTILE SHALL HAVE A PUNCTURE RESISTANCE OF 150 LBS (0.66 KN) PER ASTM D4833 TESTING METHOD.
- 8. THE GEOTEXTILE SHALL HAVE A CBR PUNCTURE RESISTANCE OF 900 LBS (4.00 KN) PER ASTM D6241 TESTING METHOD.
- 9. THE GEOTEXTILE SHALL HAVE A UV RESISTANCE OF 70% @ 500 HRS. PER ASTM D4355 TESTING METHOD.
- 10. THE GEOTEXTILE SHALL HAVE A PERMITTIVITY RATING OF 0.05 SEC-1 PER ASTM D4491 TESTING METHOD.
- 11. THE GEOTEXTILE SHALL HAVE A WATER FLOW RATING OF 4 GPM/FT2 (160 LPM/M2) PER ASTM D4491 TESTING METHOD.
- 12. THE GEOTEXTILE SHALL HAVE A PERCENT OPEN AREA OF <1% PER CW-02215 TESTING METHOD.
- 13. THE GEOTEXTILE SHALL HAVE AN APPARENT OPENING SIZE OF 40 US STD. SIEVE (0.425 MM) PER ASTM D4751 TESTING METHOD.









RECHARGER 280HD BY CULTEC, INC. OF BROOKFIELD, CT. STORAGE PROVIDED = 9.21 CF/FT [1.83 m³/m] PER DESIGN UNIT. REFER TO CULTEC, INC.'S CURRENT RECOMMENDED INSTALLATION GUIDELINES. MAXIMUM ALLOWED COVER OVER TOP OF UNIT SHALL BE 12' (3.65 m) THE CHAMBER WILL BE DESIGNED TO WITHSTAND TRAFFIC LOADS WHEN INSTALLED ACCORDING TO CULTEC'S RECOMMENDED INSTALLATION INSTRUCTIONS.

- PAVEMENT OR FINISHED GRADE

12.0" [300 mm] SDR-35 / SCH. 40 PVC COLLAR

MAINTAIN 6.0" [150 mm] CLEARANCE BETWEEN

HEAVY DUTY LID AND PVC CLEAN-OUT CAP

6.0" [150 mm] SDR-35 / SCH. 40 PVC ENDCAP

CLEAN-OUT ADAPTER W/ SCREW-IN CAP

- 6.0" [150 mm] SDR-35 / SCH. 40 PVC RISER

- 6.0" [150 mm] SDR-35 / SCH. 40 PVC COUPLING

TRIM CHAMBER INSPECTION PORT KNOCK-OUT TO

6.0" [150 mm] SDR-35 / SCH 40 PVC

INSERTED 8" [200 mm] INTO CHAMBER)

MATCH O.D. OF 6.0" [150 mm] INSPECTION PORT PIPE


FIELD PLACED CLASS "C" CONCRETE

ALL RECHARGER 280HD HEAVY DUTY UNITS ARE MARKED WITH A COLOR STRIPE FORMED INTO THE PART ALONG THE LENGTH OF THE CHAMBER ALL RECHARGER 280HD CHAMBERS MUST BE INSTALLED IN ACCORDANCE WITH ALL APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS.

6.0" [150 mm] SDR-35 / SCH. 40 PVG ENDCAP CLEAN-OUT ADAPTER W/ SCREW-IN CAP 6.0" [150 mm] SDR-35 / SCH. 40 PVC RISER - 6.0° [150 mm] SDR-35 / SCH. 40 PVC COUPLING TRIM CHAMBER INSPECTION PORT KNOCK-OUT TO MATCH O.D. OF 6.0" [150 mm] INSPECTION PORT PIPE 6.0" [150 mm] SDR-35 / SCH 40 PVC

TOWN OF TOPSFIELD, MA SITE PLAN REVIEW AND SPECIAL PERMIT

SITE PLAN AND SPECIAL PERMIT APPROVAL SIGNA TURE



PROFESSIONAL ENGINEER FOR ALLEN & MAJOR ASSOCIATES, INC.

REV DATE DESCRIPTION

SARKIS DEVELOPMENT COMPANY 2 ELM SQUARE ANDOVER, MA 01810

PROJECT:

APPLICANT\OWNER:

RESIDENTIAL DEVELOPMENT **470 BOSTON STREET (ROUTE 1)** TOPSFIELD, MA

2165-01A DATE: 10-13-2016 PROJECT NO. N.T.S. DWG. NAME: C-2165-01A DMR | CHECKED BY:

PERMITTING

ivil & structural engineering • land surveyin vironmental consulting • landscape architecture

www.allenmajor.com 10 MAIN STREET LAKEVILLE, MA 02347-1674 TEL: (508) 923-1010

FAX: (508) 923-6309 WOBURN, MA ♦ LAKEVILLE, MA ♦ MANCHESTER, NI

THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT. CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD


SHEET No.

DRAWING TITLE: DETAILS

COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.

Copyright ©2016 Allen & Major Associates, Inc. All Rights Reserved





TOWN OF TOPSFIELD, MA SITE PLAN REVIEW AND SPECIAL PERMIT

SITE PLAN AND SPECIAL PERMIT APPROVAL	SITE PLAN AND SPECIAL PERMIT APPROVAL	SITE PLAN AND SPECIAL PERMIT APPROVAL							
			SITE	PLAN .	AND	SPECIAL	PERMIT	APPROVAL	<u>'</u>



REGISTERED LANDSCAPE ARCHITECT FOR

DATE	DESCRIPTION

SARKIS DEVELOPMENT COMPANY

RESIDENTIAL DEVELOPMENT 470 BOSTON STREET (ROUTE 1) TOPSFIELD, MA

	PROJECT NO.	2165-01A	DATE:	10-13-2016
	SCALE:	AS SHOWN	DWG. NAME:	L-1.dwg
>	DESIGNED BY:	BDB	CHECKED BY:	WB
7 1	PREPARED RV.			


Landscape Architecture, Planning, Urban Design 24 Roland Street Boston, MA 02129


THIS DRAWING HAS BEEN PREPARED IN ELECTRONIC FORMAT. CLIENT/CLIENT'S REPRESENTATIVE OR CONSULTANT MAY BE PROVIDED COPIES OF DRAWINGS AND SPECIFICATIONS ON MAGNETIC MEDIA FOR HIS/HER INFORMATION AND USE FOR SPECIFIC APPLICATION TO THIS PROJECT. DUE TO THE POTENTIAL THAT THE MAGNETIC INFORMATION MAY BE MODIFIED UNINTENTIONALLY OR OTHERWISE, ALLEN & MAJOR ASSOCIATES, INC. MAY REMOVE ALL INDICATION OF THE DOCUMENT'S AUTHORSHIP ON THE MAGNETIC MEDIA. PRINTED REPRESENTATIONS OF THE DRAWINGS AND SPECIFICATIONS ISSUED SHALL BE THE ONLY RECORD COPIES OF ALLEN & MAJOR ASSOCIATES, INC.'S WORK PRODUCT.


> PLANT LIST AND **SEEDING PLAN**


L-2


SHEET No.











PERCOLATION TEST #3

LOCATION: TP16-8

DEPTH OF PERC: 63"

PERC RATE: 4.66 MPI

PERCOLATION TEST #6

LOCATION: TP16-10

DEPTH OF PERC: 54"

PERC RATE: 7.33 MPI

PERCOLATION TEST #1

LOCATION: TP16-2

DEPTH OF PERC: 66" PERC RATE: 1.66 MPI PERCOLATION TEST #2 LOCATION: TP16-4

DEPTH OF PERC: 42"

PERC RATE: 1.00 MPI

PERCOLATION TEST #4 LOCATION: TP16-5

DEPTH OF PERC: 54"

PERC RATE: 1.00 MPI


TEST PIT NOTES:

PERCOLATION TEST #5 LOCATION: TP16-12

DEPTH OF PERC: 54"

PERC RATE: 2.33 MPI

1. SOIL SUITABILITY ASSESSMENT WAS PERFORMED BY ALEXANDER F. PARKER ON JULY 6, 2016. THE ASSESSMENT WAS WITNESSED BY THE TOPSFIELD DIRECTOR OF PUBLIC HEALTH, MR. JOHN COULON.



EAGLEBROOK ENGINEERING
& SURVEY, LLC

491 MAPLE STREET, SUITE 304 DANVERS, MASS. 01923 TEL: (978) 777-0494

470 BOSTON STREET


LOCATED IN
TOPSFIELD, MASSACHUSETTS
PREPARED FOR
SARKIS DEVELOPMENT COMPANY
2 ELM SQUARE
ANDOVER, MASSACHUSETTS

STAMP:



DATE: OCTOBER 13, 2016

REVISIONS:




DRAWN BY: BSM
CHECKED BY: KCK
SCALE: AS NOTED

PROJECT NO. 15-023

TITLE:

SDS PLAN SDS-4

ISSUED FOR PERMITTING: OCTOBER 13,2016
NOT TO BE USED FOR CONSTRUCTION



ROLLING GREEN

TOPSFIELD, MASSACHUSETTS

OCTOBER 5, 2016

PROJECT TEAM: ANDREW T. ZALEWSKI, AIA

THE MZO GROUP STONEHAM, MA



LIST OF DRAWINGS

A-1 UNIT A ELEVATIONS I

A-2 Unit A Elevations II

A-3 UNIT A FIRST FLOOR

A-4 UNIT A SECOND FLOOR

A-5 UNIT B ELEVATIONS I

A-6 UNIT B ELEVATIONS II

A-7 UNIT B FIRST FLOOR

A-8 UNIT B SECOND FLOOR

A-9 UNIT C ELEVATIONS I

A-10UNIT C ELEVATIONS II

All Unit C First Floor

A-12 UNIT C SECOND FLOOR

IThe MZO Group L





FRONT ELEVATION

1/4" = 1'-0"

Unit A

Rolling Green 470 Boston Street, Topsfield, MA



LEFT SIDE ELEVATION

1/4" = 1'-0"

The MZO GROUP

DESIGNERS • ARCHITECTS • PLANNERS

IN THE *MIQUELLE* TRADITION

October 5, 2016

92 Montvale Avenue, Suite 4350
Stoneham, Massachusetts 02180 Voice 781-279-4446 ■ Fax 781-279-4448 ■ E-Mail: mzo@mzogroup.com ■ www.mzogroup.com Sheet A-1

c COPYRIGHT 2016 M.Z.O. ARCHITECTURAL GROUP, INC. OWNS THE COPYRIGHT IN THIS DOCUMENT. NO REPRODUCTION OR OTHER USE IS ALLOWED WITHOUT THE EXPRESS WRITTEN CONSENT OF M.Z.O. ARCHITECTURAL GROUP, INC.





Unit A

1/4'' = 1'-0''

Rolling Green

Hemmingway St., Winchester, MA




The MZO GROUP

DESIGNERS • ARCHITECTS • PLANNERS
IN THE *MIQUELLE* TRADITION

October 5, 2016

Sheet A-3 92 Montvale Avenue, Suite 4350 ■ Stoneham, Massachusetts 02180 Voice 781-279-4446 ■ Fax 781-279-4448 ■ E-Mail: mzo@mzogroup.com ■ www.mzogroup.com



SECOND FLOOR

1/4" = 1'-0"

Unit A

Rolling Green

Hemmingway St., Winchester, MA



The MZO GROUP

DESIGNERS • ARCHITECTS • PLANNERS
IN THE *MIQUELLE* TRADITION

October 5, 2016

Sheet A-4





FRONT ELEVATION

1/4" = 1'-0"

Unit B

Rolling Green 470 Boston Street, Topsfield, MA



LEFT SIDE ELEVATION

1/4" = 1'-0"

The MZO GROUP

DESIGNERS • ARCHITECTS • PLANNERS

IN THE *MIQUELLE* TRADITION


October 5, 2016

Sheet A-5

Voice 781-279-4446 ■ Fax 781-279-4448 ■ E-Mail: mzo@mzogroup.com ■ www.mzogroup.com

c COPYRIGHT 2016 M.Z.O. ARCHITECTURAL GROUP, INC. OWNS THE COPYRIGHT IN THIS DOCUMENT. NO REPRODUCTION OR OTHER USE IS ALLOWED WITHOUT THE EXPRESS WRITTEN CONSENT OF M.Z.O. ARCHITECTURAL GROUP, INC.





1/4'' = 1'-0''

Unit B

Rolling Green Hemmingway St., Winchester, MA



The MZO GROUP

DESIGNERS - ARCHITECTS - PLANNERS
IN THE *MIQUELLE* TRADITION


October 5, 2016

Sheet A-7

92 Montvale Avenue, Suite 4350 ■ Stoneham, Massachusetts 02180

NO REPRODUCTION OR OTHER USE IS ALLOWED WITHOUT THE EXPRESS WRITTEN CONSENT OF M.Z.O. ARCHITECTURAL GROUP, INC.

Voice 781-279-4446 ■ Fax 781-279-4448 ■ E-Mail: mzo@mzogroup.com ■ www.mzogroup.com



SECOND FLOOR

1/4" = 1'-0"

Unit B

Rolling Green Hemmingway St., Winchester, MA



The MZO GROUP

DESIGNERS - ARCHITECTS - PLANNERS
IN THE MIQUELLE TRADITION

October 5, 2016

Sheet A-8





FRONT ELEVATION

1/4" = 1'-0"

Unit C

Rolling Green 470 Boston Street, Topsfield, MA



LEFT SIDE ELEVATION

1/4" = 1'-0"

The MZO GROUP

DESIGNERS • ARCHITECTS • PLANNERS

IN THE *MIQUELLE* TRADITION

October 5, 2016

Voice 781-279-4446 ■ Fax 781-279-4448 ■ E-Mail: mzo@mzogroup.com ■ www.mzogroup.com

Sheet A-9

c COPYRIGHT 2016 M.Z.O. ARCHITECTURAL GROUP, INC. OWNS THE COPYRIGHT IN THIS DOCUMENT. NO REPRODUCTION OR OTHER USE IS ALLOWED WITHOUT THE EXPRESS WRITTEN CONSENT OF M.Z.O. ARCHITECTURAL GROUP, INC.





BACK ELEVATION

1/4" = 1^1-0 "

Unit C

Rolling Green 470 Boston Street, Topsfield, MA



RIGHT SIDE ELEVATION

1/4" = 1'-0"

The MZO GROUP

DESIGNERS • ARCHITECTS • PLANNERS


IN THE *MIQUELLE* TRADITION

October 5, 2016

Voice 781-279-4446 ■ Fax 781-279-4448 ■ E-Mail: mzo@mzogroup.com ■ www.mzogroup.com

Sheet A-10


c COPYRIGHT 2015 M.Z.O. ARCHITECTURAL GROUP, INC. OWNS THE COPYRIGHT IN THIS DOCUMENT. NO REPRODUCTION OR OTHER USE IS ALLOWED WITHOUT THE EXPRESS WRITTEN CONSENT OF M.Z.O. ARCHITECTURAL GROUP, INC.



1/4" = 1'-0"

Unit C

Rolling Green Hemmingway St., Winchester, MA




The MZO GROUP

DESIGNERS • ARCHITECTS • PLANNERS
IN THE *MIQUELLE* TRADITION

92 Montvale Avenue, Suite 4350 ■ Stoneham, Massachusetts 02180

October 5, 2016

Sheet A-11 Voice 781-279-4446 ■ Fax 781-279-4448 ■ E-Mail: mzo@mzogroup.com ■ www.mzogroup.com




SECOND FLOOR

1/4" = 1'-0"

Unit C

Rolling Green Hemmingway St., Winchester, MA



The MZO GROUP

DESIGNERS • ARCHITECTS • PLANNERS
IN THE *MIQUELLE* TRADITION

Voice 781-279-4446 ■ Fax 781-279-4448 ■ E-Mail: mzo@mzogroup.com ■ www.mzogroup.com

October 5, 2016

Sheet A-12

c COPYRIGHT 2014 M.Z.O. ARCHITECTURAL GROUP, INC. OWNS THE COPYRIGHT IN THIS DOCUMENT. NO REPRODUCTION OR OTHER USE IS ALLOWED WITHOUT THE EXPRESS WRITTEN CONSENT OF M.Z.O. ARCHITECTURAL GROUP, INC.

92 Montvale Avenue, Suite 4350
Stoneham, Massachusetts 02180